

SECTION

COPY

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #36
NOVESTA TWP.
94 NOV -9 PM 2:17
VIRGINIA H. MCLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

For corners in NOVESTA TOWNSHIP

TUSCOLA (County)	Located In:	Corner Code #:
1. Public Land Survey	T 13N R 11E	M-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Lionel Roy Emery, in a field survey on July 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1834 (Gov't. Land Office Notes) Harvey Parke, D.S., -Set post cor. Secs. 12 & 13- Hemlock 16 N15W 4½; Birch 14 S23W 16½
1889 (Resurvey of Evergreen Twp., T13N-R12E, Sanilac County) F.F. Rogers, Surveyor -Set Vitriified Stone 'corner' 3 inches in diameter and 3 feet in the Earth- gives no accessories--set from found B.T.
1892 (County Surveyor's Record, pages 196 and 197, Tuscola County) G.B. Felton -Previously set- Metal post at corner
1975 (Land Corner Recordation Certificate, Sanilac County) James A. Beck, P.S. 21559 -Fnd. remains of Cedar Post, set re-rod w/cap 11192 in center of post-N45°E 67.70' spike in 6" Pine; N20°W 65.68' Spike in 8" Cherry; ---See over for continuation of Section A.---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found ½" diameter 18" long reinforcing rod with illegible plastic cap driven into limb of buried tree trunk. Found trunk of tree buried transverse in roadbed at 30"+/- depth.

Accepted found iron as marking original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Removed found iron and a portion of tree trunk and replaced iron with Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M5 T13N/R11E
N65°E, 75.45' -T.C. Re-mon. tag in Southeast face of 16" White Pine
N74°E, 68.10' -T.C. Re-mon. tag in Northwest face of 18" White Pine
S30°E, 55.15' -T.C. Re-mon. tag in Southwest face of 8" Elm
N65°W, 45.66' -Punch mark in top of pipe cap at top of gate post
N15°W, 67.61' -T.C. Re-mon. tag above found nail in East face of 18" multi-trunk Cherry

Signed by Lionel Roy Emery Date Oct. 10, 1994
Surveyor's Michigan License No. 24593

APPROVED
10-10-94

1600
gms
gml



