

COPY

SECTION

1994 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in NOVESTA TOWNSHIP

<u>TUSCOLA</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T 13N R 11E	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. #39  
NOV 9 9 94 NOV 9 94 PM 2:18  
VIRGINIA M. HCLAREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

Lionel Roy Emery, in a field survey on July 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S. Set qr. Sec. post- Sugar 20 S49W 20; Hemlock 6 N28W 57 1/2
  - 1889 (Resurvey of Evergreen Twp., T13N-R12E, Sanilac County) F.F. Rogers, Surveyor -Set Vitriified Stone 'corner' 3 inches in diameter and 3 feet in the Earth- gives no accessories.
  - 1895 (County Surveyor's Record pages 140 and 141, Sanilac County) M.E. Ward, Surveyor -shows "crook" previously set by Rogers- gives no accessories.
  - 1972 (Survey -Liber 2 of Surveys, pages 130 and 131, Sanilac County) David T. Rowe, P.S. 11192 -Set "T" Iron- West 84.94' RLS tag in PP; N40°W, 45.39' Nail & Cap in TP; S15°E, 99.30' RLS Tag in 8" tree


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found "T" Iron and 30" of 3" diameter "Vitrified Stone" --Vitrified Stone in two sections-- top section had upper 6"+/- broken off, bottom section (1 ft.) had cross cast in top.

Accepted found objects as marking original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Removed found objects and replaced with Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M8 T13N/R11E  
N82°E, 40.40' -T.C. Re-mon. tag in South face of 6" Twin Elm  
S40°E, 50.99' -T.C. Re-mon. tag in Southwest face of 7" Locust  
S24°W, 46.57' -T.C. Re-mon. tag in Northwest face of 5" Ash  
West, 85.28' -T.C. Re-mon. tag in North face of Power Pole (also found tag 11192 in East face)

Signed by Lionel Roy Emery Date Oct. 10, 1994  
Surveyor's Michigan License No. 24593

APPROVED  
10-10-94



1975 (Land Corner Recordation Certificate, Sanilac County) James A. Beck, P.S. 21559 --Found bits of iron & decayed wood at 30" deep , perpetuated with 2' x 1/2" iron rod- S70 E, 71.77' nail & Tag in root 18" Maple; S45 E 39.21' spike in center 30" stump; S50 W 74.59' nail & tag in PP; N55 W 63.24' nail & tag in Tel. Pole

1975 (Survey, Liber 3, pages 322 and 323, Sanilac County) James A. Beck, P.S. 21559 --corner marker and accessories same as Land Corner Recordation Certificate.

SURVEY &  
DOCUMENTATION

COPY

DEC 28 2000

SECTION

