

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 37
FILE NO. WISNER TWP
96 DEC 26 AM 11:49
Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in **WISNER TWP.**
TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 14N R 07E _____ B-13 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on DECEMBER 16 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below;

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; W. ASH 12 S45E 90LKS, ELM 12 S39W 1.10LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. NO EVIDENCE OF MONUMENT AT CORNER; REESTABLISHED POSITION FOR CORNER BY SINGLE PRORATION OF GLO DIST. BETWEEN M-13 & E-13 T14N-R7E (21120 GLO VS. 21120.087 MEASURED) & ON LINE FROM A-13 TO C-13 T14N-R7E

ACCEPTED PRORATED POSTION AS PROPER REESTABLISHMENT OF ORIGINAL CORNER LOCATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-13 SET STANDARD REMON MONUMENT STAMPED "B 13 T14N R7E"

- N10°W, 37.42' SET 1/2" ROD W/CAP #37276
- N13°W, 22.21' SET 1/2" ROD W/CAP #37276
- N15°E, 39.12' SET 1/2" ROD W/CAP #37276
- N60°E, 21.25' SET 1/2" ROD W/CAP #37276
- N64°W, 9.80' SET 1/2" ROD W/CAP #37276

- EAST, 35'+/- C/L DITCH TO N.
- EAST, 8'+/- C/L DITCH TO S.
- WEST, 2'+/- C/L BERM TO N.

WEST, 1.0' SET CARSONITE WITNESS POST

Signed by Jonathan M. Field Date 12-24-96
Surveyor's Michigan License No. 37276

APPROVED
12-23-96

*ADD
R&B
L.P.E.*



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 1971
REVISED JAN 1975
REVISED JAN 1983
REVISED JAN 1993
ADAPTED FOR VIDEO PROCESSING

RECORDED
INDEXED
FEB 20 1997
TUSCOLA COUNTY

