

**1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
LIBER NO. 38 PAGE NO. 38  
FILE NO. WISNER TWP  
95 DEC 26 AM 11:49  
TUSCOLA COUNTY  
REGISTER OF DEEDS

For corners in WISNER TWP.  
TUSCOLA  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 14N R 07E \_\_\_\_\_ C-13 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on DECEMBER 16 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLO; RISDON, D.S.; SET POST; ELM 12 N72E 22LKS, LYNN 20 N85W 41LKS  
1917 BRUMLEY, MINUTES OF SURVEY FOR NORTHWEST DRAIN OUTLET NO.2; BK.26, PG.28 TUSCOLA CO.  
DRAIN NOTES; DRAIN COMMENCES 0.39 CH. S. & 0.25 CH. E. OF NW COR. SEC.5 T13N-R7E THENCE RUNS E'LY  
1977 WITNESS CARD AT ROWE ENG.; 1" THREADED STUD IN NW BRIDGE WINGWALL; N35W 95.20' RLS TAG 11192 IN P.POLE, N80W 45.58' FACE OF ROAD SIGN POST, WEST 29' C/L GRAVEL N-S, SOUTH 17' C/L GRAVEL EAST NOTE ON CARD STATES "THIS MAY NOT BE THE SEC. CORNER"

GLO NOTES OF T13N-R7E INDICATE THAT THIS CORNER IS NOT COMMON WITH C-1 T13N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 ROWE ENG.; FIELD, P.S.#37276; FND 1" THREADED STUD IN NW BRIDGE WINGWALL; DID NOT ACCEPT AS PROPER POSITION FOR CORNER; REESTABLISHED CORNER POSITION BY SINGLE PRORATION OF GLO DIST. BETWEEN M-13 & E-13 T14N-R7E (21120' GLO VS. 21120.087 MEAS.) & ON LINE FROM B-13 TO D-13 T14N-R7E

POSITION FIT 1917 CALL TO C/L OF DRAIN W/IN 2-4'

ACCEPTED PRORATED POSITION AS PROPER REESTABLISHMENT OF ORIGINAL CORNER LOCATION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SET STANDARD REMON MONUMENT STAMPED "C 13 T14N R7E"  
N21°E, 28.35' SET 1/2" ROD W/CAP #37276  
N72°E, 49.29' SET CHIS. + ON CONC. WINGWALL  
N41°E, 65.85' FND. 1" THREADED ROD IN CONC. WINGWALL  
N75°W, 12.24' SET NAIL W/TAG #37276 IN SE FACE 8" ASH  
N02°W, 132.00' FND. NAIL W/TAG #11192 IN S. FACE P.POLE



Signed by Jonathan M. Field Date 12-24-96  
Surveyor's Michigan License No. 37276

APPROVED  
12-23-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1993  
ADAPTED FOR WORD PROCESSING MARCH, 1993

MAY 2 9 1997

