

**1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
 LIBER NO. \_\_\_\_\_ PAGE NO. 41  
 FILED IN Wisner Twp  
 96 DEC 26 AM 11:49  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

For corners in WISNER TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>07E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		16	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1834 GLO; RISDON, D.S.; SET POST; B. ASH 12 N34E 3LKS, B. ASH 14 N64W 27LKS  
 1902 FELTON, C.S.; SURVEY OF SEC.34, T14N-R7E PREV. SET CEDAR POST AND STONES. NO WITS GIVEN

GLO NOTES OF T13N-R7E INDICATE THAT THIS CORNER IS NOT COMMON WITH G-1 T13N-R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1996 ROWE ENG.; FIELD, P.S.#37276; FND. NO EVIDENCE OF MONUMENT AT CORNER; REESTABLISHED POSITION FOR CORNER BY PRORATION TO 1902 FELTON SURVEY USING DIST. FROM G-12 TO G-11 T14N-R7E AND HOLDING LINE FROM G-12 THROUGH FND. NAIL AT OCCUPIED C/L OF AKRON ROAD CORNER POSITION FALLS IN STEEP DITCH BANK - SET WITNESS MONUMENT ON LINE G-13 TO G-12 T14N-R7E 19.04' N. OF G-13

ACCEPTED PROPORTION TO 1902 CO. SURVEY AS PROPER REESTABLISHMENT OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 G-13 SET WITNESS MONUMENT (STANDARD REMONUMENT STAMPED "W.C. G 13 T14N R7E" IN MON. BOX WITNESSES ARE TO WITNESS MONUMENT NOT CORNER G-13 (WITNESS CORNER)  
 N60°W, 25.29' SET 1/2" ROD W/CAP #37276  
 S55°W, 21.86' SET 1/2" ROD W/CAP #37276  
 S28°E, 117.22' SET P-K NAIL W/TAG #37276 IN E. FACE P.POLE  
 N55°E, 71.64' SET P-K NAIL W/TAG #37276 IN NW FACE P.POLE  
 N70°E, 39.12' SET P-K NAIL IN ASPH.  
 EAST, 39.79' FND. NAIL IN ASPH.



Signed by Jonathan M. Field Date 12-24-96  
 Surveyor's Michigan License No. 37276

APPROVED  
12-23-96  
 J.M.F.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

MAY 20 1997

