

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 44
TUSCOLA COUNTY REGISTER OF DEEDS
96 DEC 26 AM 11:49
Jonathan M. Field

For corners in **WISNER TWP.**

TUSCOLA Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T 14N R 07E _____ K 13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; W. MAPLE 12 N63E 43LKS, B. ASH 18 N35W 44LKS
1972 ROWE ENG, ROWE, P.S.#11192; SURVEY L.2, PG.419; SET T IRON; N50E, 74.55' RLS TAG 11192 IN P/P, N55W 81.22' RLS TAG 11192 IN P/P, WEST 18' C/L GARNER RD., N75E 70.65' RD SIGN POST

GLO NOTES FOR T13N-R7E INDICATE THAT THIS CORNER IS NOT COMMON WITH K-1 T13N-R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. T-IRON 18' E. OF C/L ASPH. ROAD TO N.; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND T-IRON IS IN SAME POSITION AS 1972 SURVEY CITED ABOVE

ACCEPTED FND. T-IRON AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-13 REMOVED T-IRON, SET STANDARD REMON MONUMENT STAMPED "K 13 T14N R7E" IN MON. BOX
N60°E, 74.55' FND. NAIL W/TAG #11192 IN SW FACE P.POLE
N65°W, 81.22' FND. NAIL W/TAG #11192 IN SE FACE P.POLE
S55°E, 20.31' NW CORNER OF CONC. GUARD RAIL POST
S45°W, 44.03' NE CORNER OF CONC. GUARD RAIL POST
EAST, 4.62' FND. 1/2" ROD AT APPARENT K-1 T13N-R7E



Signed by *Jonathan M. Field* Date 12-16-96
Surveyor's Michigan License No. 37276

APPROVED
12-11-96
1100 RAB J.P.E.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

RECORDED
JAN 20 1997
TUSCOLA COUNTY

