

**1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **WISNER TWP.**

<u>TUSCOLA</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>07E</u>	<u>L 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. 45  
FILE NO. Wisner Twp.  
96 DEC 26 AM 11:49  
TUSCOLA COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLO; RISDON, D.S.; SET POST; B. ASH 10 N68E 27LKS, ELM 16 N46W 36LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 ROWE ENG.; FIELD, P.S.#37276; FND. NO EVIDENCE OF MONUMENT AT CORNER LOCATION; REESTABLISHED POSITION OF CORNER BY SINGLE PROPORTION BETWEEN K-13 & M-13 T14N-R7E POSITION THUS ESTABLISHED FALLS ON FIELD DIVISION LINE N-S & 9' S. OF C/L ASPH. ROAD E-W

ACCEPTED SINGLE PROPORTION POSITION AS PROPER REESTABLISHMENT OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-13 SET STANDARD REMON MONUMENT STAMPED "L 13 T14N R7E" IN MON. BOX  
S80°E, 29.57' SET 1/2" ROD W/CAP #37276  
S75°W, 26.00' SET 1/2" ROD W/CAP #37276  
N55°W, 35.85' SET 1/2" ROD W/CAP #37276  
N45°E, 35.15' SET 1/2" ROD W/CAP #37276

Signed by Jonathan M. Field Date 12-16-96  
Surveyor's Michigan License No. 37276



APPROVED  
12-11-96  
R.P.B.  
L.P.E.

REMONUMENTATION  
MAY 20 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

