

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
USER NO. 11-27-96 PAGE NO. 28
WISNER
55 DEC 10 AM 9:00

For corners in WISNER TWP.

TUSCOLA Located In: Corner Code #

1. Public Land Survey T 14N R 07E
T R
T 14N R 8E
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

M-9
A-9

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; W. OAK 16 N20W 14LKS, SYCAMORE 30 S46W 48 LKS
1902 FELTON, C.S.; PREV. SET POST, STONE AND CROCKERY; APPLE 3 S51E 1.21CHS, SUGAR 4 S25 1/4E 1.25LKS
1974 LEACH, P.S.#7236; LCRC PG.16; FND 1/2"x 3 1/2" IRON BAR; N85E 14.50' SW COR BRIDGE DECK N35E 31.30' NW COR BRIDGE DECK, S80W 71.10' BOLT IN E FACE P/P
1975 KAY, P.S.#14096; SURVEY L.449, PG.535; 3/8" ROD; N40E 29.03' BRIDGEPOST, S65E 27.77' BRIDGEPOST, S45W 44.67' RD SIGN POST, EAST 4.5' EDGE OF BLACKTOP
1985 DUNTON, P.S.#23503; SURVEY L.567, PG.577; SET R.R. SPIKE PER WITNESSES; SAME WITS AS 1974 LCRC ABOVE
1987 DE LA MATER, P.S.#13030; LCRC PG.16; FND. 3/8" BAR; P/P W/NAIL N45W 76.70', P/P W/NAIL S55W 67.71', NW COR WINGWALL S15W 27.41'
1995 ROWE ENG.; FIELD, P.S.#37276; SURVEY L.683, PG.10; FND. 2 1/2" PIPE IN MON BOX; N55W 76.58' FND ROOFING NAIL W/FLAG. NE FACE P/P, S50W 67.61' FND ROOFING NAIL W/FLAG. SE FACE P/P, N30E 30.86' SET CHIS "+" NLY COR NW WINGWALL, S30E 27.47' SET CHIS "+" SLY COR SW WINGWALL,

GLO NOTES FOR T14N-R8E INDICATE THAT THIS CORNER IS COMMON WITH A-9 T14N-R8E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 2 1/2" PIPE IN MON. BOX 10.5' E. OF C/L ASPH. ROAD N-S & 2' S. OF C/L GRAVEL ROAD E-W; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. PIPE IS IN SAME POSITION AS 1975 SURVEY CITED ABOVE

ACCEPTED FND. PIPE IN MON. BOX AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9 SET 5/8" ROD W/ STANDARD REMON CAP STAMPED "M 9 T14N R7E" INSIDE FND. PIPE ENCASED BOTH IN CONC. IN MON. BOX
N55°W, 76.58' SET NAIL W/REMON TAG IN NE FACE P. POLE
S50°W, 67.61' SET NAIL W/REMON TAG IN SE FACE P. POLE
N30°E, 30.86' FND. CHIS "+" NLY COR NW WINGWALL
S30°E, 27.47' FND. CHIS "+" SLY COR SW WINGWALL
N55°E, 29.03' SW CORNER OF C-CHANNEL STEEL BRIDGE RAIL POST
S65°E, 27.77' NW CORNER OF C-CHANNEL STEEL BRIDGE RAIL POST

Signed by *Jonathan M. Field* Date 11-29-96
Surveyor's Michigan License No. 37276

APPROVED
11-27-96



MAY 20 1997

