

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED FOR RECORD
LIBER NO. _____ PAGE NO. 27
FILE NO. Wisner

95 DEC 10 AM 9:00

For corners in WISNER TWP.

TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 14N R 7E _____ M-10
T _____ R _____ _____
T 14N R 8E _____ A-10
T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

[Signature]
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; ELM 10 S52W 24LKS, ELM 18 N51W 35LKS
1974 LEACH, P.S.#7236; LCRC PG.14; SET T IRON ON STEEP BANK ON W SIDE DITCH AT INTERSECTION OF 1/4 LINE FENCE W/ SECTION LINE; W. 20.42' C/L ROAD, W. 70.10' N. FACE T.POLE
1987 DE LA MATER, P.S.#13030; LCRC PG.16; FND 3/8" BAR; S60W 59.91' P/P, S60E 56.24' 10" P.V.C. DRAIN PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 3/8" ROD 14' E. OF C/L ASPH. ROAD N-S & ON OCCUPIED FIELD DIVISION E-W; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. 3/8" ROD IS IN SAME POSITION AS 1987 LCRC ABOVE

ACCEPTED FND. 3/8" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-10 REPLACED FND. 3/8" ROD W/ STANDARD REMON MONUMENT STAMPED "M 10 T14N R7E" IN MON BOX WEST, 60.12' SET NAIL W/REMON TAG IN N. FACE P.POLE
S60°E, 56.24' 10" PVC DRAIN TILE
N36°W, 48.40' SET 1/2" ROD W/CAP #37276
S25°W, 58.29' SET 1/2' ROD W/CAP #37276
N05°W, 34.00' SET 1/2" ROD W/CAP #37276

NOTE: THIS CORNER IS COMMON WITH A-10 T14N-R8E

Signed by Jonathan M. Field Date 11-29-96
Surveyor's Michigan License No. _____



APPROVED
11-27-96
[Signature]

MAY 2 1997

79

