

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 86
FILE NO. S. Akron

95 DEC 10 AM 8:58

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in S. AKRON TWP.

TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 14N R 08E _____ A-7 ✓
T _____ R _____ _____
T 14N R 7E _____ M-7
T _____ R _____ _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 GLO; RISDON, D.S.; SET AS M-7 OF THE ORIGINAL GOVERNMENT SURVEY OF T14N-R7E; POST IN MARSH; NO WITS GIVEN
 - 1887 TESKEY, C.S.; SURVEY OF SEC.18 T14N-R8E; PREV ESTABLISHED CEDAR STAKE AND CROCKERY; MAPLE 1 N45E 51LKS
 - 1902 FELTON, C.S.; SURVEY OF SEC.19 T14N-R8E; PREV SET POST AND CROCKERY; MAPLE 8 N55E 51LKS
 - 1971 KAY ENG.; KAY, P.S.#14096; SURVEY L.1, PG.143; NO OBJECT STATED; NO WITS GIVEN
 - 1978 GRAVLIN, P.S.#23510; SURVEY L.496, PG.1478-9; PK NAIL; WEST 13.7' C/L RD, N60W 53.42' JUNCTION BOX, N40E 22.3' NE ANGLE POINT WINGWALL, S45E 19.6' SE ANGLE POINT WINGWALL
 - 1980 LEACH, P.S.#7236; LCRC PG.11; FND MON BOX WITH IRON; N50E 20.80' SE COR HDWL, S50E 18.30' NE COR HDWL, N60W 54.10' TOP TELE RISER, S45W 83.40' NAIL W/ TAG IN P/P
 - 1980 LEACH, P.S.#7236; SURVEY L.507, PG.496; FND. MON BOX; SAME WITS AS 1980 LCRC ABOVE
 - 1984 DUNTON, P.S.#23503; SURVEY L.541, PG.916; NO OBJECT STATED; NO WITS GIVEN
 - 1984 ROWE ENG.; FOLKENS, P.S.#21567; SURVEY L.542, PG.371; FND BOLT W/ NUT IN MON BOX; SAME WITS AS 1980 LCRC ABOVE
 - 1985 GRAVLIN, P.S.#23510; SURVEY L.557, PG.795; NO OBJECT STATED; WEST 13.70' C/L RD., N60W 53.42' JUNCTION BOX, N40E 22.3' NE ANGLE POINT WINGWALL, S45E 19.6' SE ANGLE POINT WINGWALL
 - 1987 ROWE ENG.; BROWN, P.S.#33134; SURVEY L.580, PG.812; SET PK; WEST 14.49' FND PK IN PAVT, N70W 78.5' FND PK IN P/P, S45W 83.41' FND PK IN P/P, N10E 26.49' SET TAG #11192 TOP GUARD RAIL POST
 - 1987 ROWE ENG.; BROWN, P.S.#33134; SURVEY L.580, PG.818; FND PK NAIL; SAME WITS AS 1987 SURVEY

GLO NOTES OF T14N-R8E INDICATE THAT THIS CORNER IS COMMON WITH M-7 T14N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996 ROWE ENG.; FIELD, P.S.#37276; FND. EMPTY MON. BOX 1' S. OF C/L ASPH. ROAD E-W & 18.5' E. OF C/L ASPH. ROAD N-S; RECOVERED 1 PREVIOUS WITNESSES WHICH INDICATES THAT FND. MON BOX IS IN SAME POSITION AS 1980 LCRC CITED ABOVE
- ACCEPTED CENTER OF FND. MON. BOX AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-7 SET 5/8" ROD W/ STANDARD REMON CAP STAMPED "M 7 T14N R7E" IN CENTER OF MON. BOX ENCASED ROD & CAP IN CONC.
 - S50°W, 83.43' SET NAIL W/REMON TAG IN NW FACE P.POLE
 - N70°W, 78.37' SET NAIL W/REMON TAG IN NE FACE P.POLE
 - N10°E, 26.49' FND. NAIL W/TAG #11192 IN TOP OF GUARD RAIL POST
 - S40°E, 25.50' SET NAIL W/REMON TAG IN TOP OF GUARD RAIL POST

Signed by *Jonathan M. Field* Date 12-4-96
Surveyor's Michigan License No. 37276



APPROVED
12-2-96
J.M.F.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 1971
REVISED MARCH, 1976
REVISED JAN. 1983
ADAPTED FOR THE 1996 ACT 74, MARCH, 1993

COMMISSION
REMONUMENTATION

MAY 20 1997

COMMISSION

