

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 84
REC'D BY S. AKRON

96 DEC 10 AM 8:58

For corners in S. AKRON TWP.

TUSCOLA Located In: _____ Corner Code # _____
(County)

- | | | |
|---------------------------------------|---------------------------|--------------|
| 1. Public Land Survey | T <u>14N</u> R <u>08E</u> | <u>A-9</u> ✓ |
| | T _____ R _____ | _____ |
| | T <u>14N</u> R <u>7E</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Gregory M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MAY 21 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 GLO; RISDON, D.S.; SET AS M-9 OF THE ORIGINAL GOVERNMENT SURVEY OF T14N-R7E; POST; W. OAK 16 N20W 14LKS, SYCAMORE 30 S46W 48 LKS
 - 1902 FELTON, C.S.; PREV. SET POST, STONE AND CROCKERY; APPLE 3 S51E 1.21CHS, SUGAR 4 S25 1/4E 1.25LKS
 - 1974 LEACH, P.S.#7236; LCRC PG.16; FND 1/2"x 3 1/2" IRON BAR; N85E 14.50' SW COR BRIDGE DECK N35E 31.30' NW COR BRIDGE DECK, S80W 71.10' BOLT IN E FACE P/P
 - 1975 KAY, P.S.#14096; SURVEY L.449, PG.535; 3/8" ROD; N40E 29.03' BRIDGEPOST, S65E 27.77' BRIDGEPOST, S45W 44.67' RD SIGN POST, EAST 4.5' EDGE OF BLACKTOP
 - 1985 DUNTON, P.S.#23503; SURVEY L.567, PG.577; SET R.R. SPIKE PER WITNESSES; SAME WITS AS 1974 LCRC ABOVE
 - 1987 DE LA MATER, P.S.#13030; LCRC PG.16; FND. 3/8" BAR; P/P W/NAIL N45W 76.70', P/P W/NAIL S55W 67.71', NW COR WINGWALL S15W 27.41'
 - 1995 ROWE ENG.; FIELD, P.S.#37276; SURVEY L.683, PG.10; FND. 2 1/2" PIPE IN MON BOX; N55W 76.58' FND ROOFING NAIL W/FLAG. NE FACE P/P, S50W 67.61' FND ROOFING NAIL W/FLAG. SE FACE P/P, N30E 30.86' SET CHIS "+" NLY COR NW WINGWALL, S30E 27.47' SET CHIS "+" SLY COR SW WINGWALL,

GLO NOTES FOR T14N-R8E INDICATE THAT THIS CORNER IS COMMON WITH M-9 T14N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996 ROWE ENG.; FIELD, P.S.#37276; FND. 2 1/2" PIPE IN MON. BOX 10.5' E. OF C/L ASPH. ROAD N-S & 2' S. OF C/L GRAVEL ROAD E-W; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. PIPE IS IN SAME POSITION AS 1975 SURVEY CITED ABOVE
- ACCEPTED FND. PIPE IN MON. BOX AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-9 SET 5/8" ROD W/ STANDARD REMON CAP STAMPED "M 9 T14N R7E" INSIDE FND. PIPE ENCASED BOTH IN CONC. IN MON. BOX
 - N55°W, 76.58' SET NAIL W/REMON TAG IN NE FACE P.POLE
 - S50°W, 67.61' SET NAIL W/REMON TAG IN SE FACE P.POLE
 - N30°E, 30.86' FND. CHIS "+" NLY COR NW WINGWALL
 - S30°E, 27.47' FND. CHIS "+" SLY COR SW WINGWALL
 - N55°E, 29.03' SW CORNER OF C-CHANNEL STEEL BRIDGE RAIL POST
 - S65°E, 27.77' NW CORNER OF C-CHANNEL STEEL BRIDGE RAIL POST

Signed by Jonathan M. Field Date 11-29-96
Surveyor's Michigan License No. 37276

APPROVED
11-27-96
L.P.E.
R.L.B.



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED JAN. 24, 1975
REVISED JAN. 1983
REVISED FOR WORD PROCESSING MARCH, 1993

SURVEY &
REMONUMENTATION

MAY 20 1997

COMMISSION

