

1993

1993 REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
S. AKRON TOWNSHIP

For corners in

TUSCOLA
(County)

Located In:

Corner Code --#

- 1. Public Land Survey T 14N R 8E M-6
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORDS
 LIBRARY PAGE NO 24
 FILED IN S Akron
 93 DEC 10 PM 12:02
 MICHIGAN STATE BOARD OF LAND SURVEYORS
 TUSCOLA COUNTY REGISTER OF DEEDS

I, Kenneth D. Dunton, in a field survey on Sept. 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes
 Joseph Wampler, D.S.
 Set 1/2 mile post
 Beech 14" S13°W 8.58'
 Beech 10" N12°E 15.18'

May 14, 1980 Act 74, T14N-R8E, Page 46 by Douglas W. Hooth, R.L.S. #7966. Dug holes & searched for evidence, found nothing. Set 3/4" re-rod in mon. box by single proportion between SE & NE corners of Sec. 13, T14N-R8E.
 S02°39'W W 1/4 cor. 19 14.30'
 N80°E SW cor. barn fnd. 116.00'
 S86°W t. pole 51.33'
 East edge bit. M-138 7.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted 1" O.D. pipe in mon. box per Act 74 by Hooth, May 14, 1980, T14N-R8E, Page 46.

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 2" brass cap stamped corner M-6, T14N-R8E over 1" pipe in existing mon. box. Encased pipe & cap in concrete.
 S04°31'W 14.33' found 1" O.D. pipe in mon. box. Apparent cor. A-8, T14N-R9E.
 S49°30'W 61.62' chiseled "+" atop S. end of 50' of 12" CSP drive culvert.
 N77°22'W 45.23' chiseled "+" atop N. end of 50' of 12" CSP drive culvert.
 N32°08'E 105.50' found "+" atop conc. hdwl. between letters NE + CE, Oct. 8, 1988.
 N80°23'E 115.94' SW corner barn footings.
 S86°56'E 22.05' set 1/2" x 24" rod & cap # 23503.

Signed by

[Signature]

Date Nov. 22, 1993

Surveyor's Michigan License No.

23503

APPROVED
11-22-93

[Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971, REVISED MAY 14, 1975, REVISED JAN., 1983



