

1993

1993 REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
S. AKRON TOWNSHIP

RECEIVED FOR RECORD  
LIBERATION PAGE NO. 69  
FILING NO. S. Akron  
93 DEC 10 PM 12:01  
VIRGINIA H. FORTABACH  
TUSCOLA COUNTY  
REGISTER OF DEEDS

For corners in

TUSCOLA

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	14N	R	8E	M-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on Sept. 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes  
Joseph Wampler, D.S.  
Set post corner Sec. 25 & 36  
Ash 30" S42°W 16.50'  
Beech?" N40°E 30.36'

May 24, 1980 Act 74, T14N-R8E, Page 51 by Douglas W. Hooth, R.L.S. #7966 (with Mich. Dept. of Trans.).  
Dug hole - found no evidence of cor.  
Ackerman plug set by M.S.H.D. gone. Set cor. from 1963 Road Comm. files (Tuscola) witnesses & 1970 M.S.H.D. witnesses. Set 1/2" steel bar in mon. box.  
S02°50'W Sec. cor. common to Sec's 6 Almer & 31 Columbia Twp. 104.27'  
N55°E p.p. 36.34'  
N81°E NW cor. house foundation 65.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S62°E SW cor. house fnd. 67.70'  
East E.M.-M-138 10.2'

Found and accepted 5/8" re-rod in mon. box per Act 74 of record.

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 2" brass cap stamped corner M-11, T14N-R8E, over 5/8" rod in existing mon. box.  
Encased rod & cap in concrete.  
S02°50'20"W 104.32' Found 5/8" reroed in mon. box at apparent corner A-1, T13N-R9E.  
N32°10'E 95.38' Set T.C. remon. tag and spike in W. face P.pole.  
N79°30'E 65.03' NW corner house footings.  
S65°27'E 67.73' SW corner house footings.  
S86°45'E 20.00' set 1/2" reroed in road shoulder.

Signed by [Signature]  
Surveyor's Michigan License No. 23503

Date Nov. 1, 1993

APPROVED  
11-1-93  
J.P.E.  
J.M.F.  
A.S.M.

STATE OF MICHIGAN  
KENNETH D. DUNTON  
LAND SURVEYOR  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
23503 REVISED MAY 14, 1975  
REVISED JAN., 1983

**COPY**

