

**1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: COLUMBIA TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>09E</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JULY 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1835 GLO; PARKE, D.S.; SET POST; W.OAK 40 N17E 51LKS., BEECH 14 S21E 38LKS.  
1980 HOOTH, LS#7966; LCRC PG.32; FND. AKERMAN PLUG SET BY MDSH IN 1969, REPLACED W/ 1/2" BAR (IN MON BOX); N03E 104.27' NE COR. SEC.36, N47E 100.72' SW COR PORCH, N60E 60.67' 16" ASH, S20E 65.08' P.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1980 HOOTH LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND ROD AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-13 REPLACED 1/2" ROD W/ 5/8" ROD & STANDARD REMON CAP STAMPED A 13 T14N R9E IN CONC. IN MON. BOX  
NORTH, 104.31' FND. TUSCOLA CO. MONUMENT AT M-11 T14N-R8E  
N54°E, 60.88' NAIL W/TAG #37276 IN NW FACE 20" ASH (SET NAIL W/TAG)  
S40°E, 73.41' P-K NAIL W/TAG #37276 IN SW FACE P.POLE (SET P-K NAIL W/TAG)  
S55°W, 34.74' 1/2 ROD W/CAP #37276 (SET ROD W/CAP)  
N32°W, 58.18' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)  
N44°E, 100.70' SW CORNER CONC. BLOCK FOUNDATION

NOTE: THIS CORNER IS COMMON WITH A-1 T13N-R9E

Signed by Jonathan M. Field Date 10-7-97  
Surveyor's Michigan License No. 37276



**APPROVED**  
9-9-97  
*[Handwritten Signature]*

SURVEY &  
REMONUMENTATION

NOV 26 1997

COMMISSION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED MARCH, 1975  
ADAPTED FOR MICHIGAN BOARD OF LAND SURVEYORS, REVISED MARCH, 1983

RECEIVED FOR RECORD  
LIBER NO. 451 PAGE NO. \_\_\_\_\_  
FILE NO. COLUMBIA TWP  
97 OCT -7 PH 3:01  
*[Handwritten Signature]*  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

2-2



UNIONVILLE ROAD 104.32' REMON '93  
104.31' REI '97  
104.28' GLO  
2479.43' REMON '93  
2479.46 REI '97

M-11  
T14N-R8E  
1993 REMON. S.AKRON TWP. PG.69

SEC. 31  
T14N-R9E

A-13 FND. 0.04' W. OF TWP. LINE AS MONUMENTED  
189°29'45" B-13

1191.62' REI '97  
1834 GLO 1191.30'

180°00'00"

90°28'55"

ELMWOOD ROAD

A-1

SEC. 6  
T13N-R9E

M-12  
T14N-R8E  
1993 REMON. S.AKRON TWP. PG.68