

**1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILED # 58  
COLUMBIA TOWNSHIP  
97 OCT -7 PM 3:01  
TUSCOLA COUNTY  
REGISTERED DEEDS

For corners in: **COLUMBIA TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>09E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1835 GLO; PARKE, D.S.; SET 1/4 SEC. POST; LYNN 9 N26W 7 1/2LKS., BEECH 10 N63E 54LKS.  
1980 HOOTH, LS#7966; LCRC PG.36; FND. 3/8" ROD IN CONC. 12" DEEP (IN MON BOX); N10W 62.75' 7" BIRCH, N45W 54.80' 6" MAPLE, S88E 38.05' N1/4 COR. SEC.6, NORTH 8.6' N. EDGE OF GRAVEL ROAD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1980 HOOTH LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND ROD AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
B-13 REPLACED 1/2" ROD W/ 5/8" ROD & STANDARD REMON CAP STAMPED B 13 T14N R9E IN CONC. IN MON. BOX EAST, 38.08' FND. 3" ROD IN MON. BOX APPARENT B-1 T13N-R9E  
N50°W, 54.61' NAIL W/TAG #37276 IN SW FACE 16" MAPLE (SET NAIL W/TAG)  
N13°W, 62.61' NAIL W/TAG #37276 IN E. FACE 12" BIRCH (SET NAIL W/TAG)  
S57°W, 29.44' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)  
S60°E, 30.77' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)



Signed by Jonathan M. Field Date 9-10-97  
Surveyor's Michigan License No. 37276

APPROVED  
9-8-97  
15DD  
JPE  
RBB

SURVEY &  
REMONUMENTATION

NOV 26 1997

COMMISSION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

