

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: **COLUMBIA TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>09E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1835 GLO; PARKE, D.S.; SET POST; B. ASH 7 N69E 39LKS., ELM 10 N80W 13LKS.
 1988 BROWN, P.S.#33134; LCRC PG.46; SET 1/2" ROD; S10E 38.64' RR SPIKE IN P.POLE, N55E 89.34' P-K NAIL IN W. FACE P.POLE, S45E 61.31' W. EDGE YIELD SIGN POST, N15W 48.10' E. EDGE YIELD SIGN POST, EAST 34.32' 1/2" PIPE AT NW COR. SEC.4
 1988 ROWE; BROWN, P.S.#33134; SURVEY L.587 PG.754-755; NO OBJECT STATED; NO WITS GIVEN, DIST. OF 34.32' SHOWN TO E-1 T13N-R9E
 1988 ROWE; BROWN, P.S.#33134; SURVEY L.587 PG.758-759; NO OBJECT STATED; NO WITS GIVEN, DIST. OF 34.32' SHOWN TO E-1 T13N-R9E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD W/CAP #20709; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1988 BROWN LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND ROD AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED E 13 T14N R9E IN MON. BOX
 EAST, 34.35' FND. 3/4" PIPE APPARENT E-1 T13N-R9E
 N52°E, 89.36' P-K NAIL IN W. FACE P.POLE (FND P-K NAIL)
 S09°E, 38.63' R.R. SPIKE IN N. FACE P.POLE (FND R.R. SPIKE)
 N45°W, 27.23' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)
 S05°E, 22.04' 1/2" ROD IN CONC. BAG HEADWALL (FND ROD)
 S58°E, 63.49' 1/2" ROD IN CONC. BAG HEADWALL (FND ROD)



Signed by Jonathan M. Field Date 9-10-97
 Surveyor's Michigan License No. 37276

**SURVEY &
REMONUMENTATION**

APPROVED
9-8-97

**NOV 26 1997
COMMISSION**

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1993
 ADAPTED FOR WORD PROCESSING MARCH, 1993

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. _____
 FILE NO. #55
COLUMBIA TOWNSHIP
 97 OCT - 7 PM 3:02

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

