

COPY

1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILE NO. # 35  
ELMWOOD TOWNSHIP  
97 OCT -9 PM 1:07

For corners in: ELMWOOD

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>10E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Gregory M. Field*  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JULY 25 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1835 GLO; PARKE, D.S.; SET 1/4 SEC. POST; MAPLE 30 N50E 5LKS., BIRCH 15 N51W 24LKS.  
1886 TESKEY, C.S.; SURVEY OF SEC. 31; ESTABLISHED AT EQUAL DIST. BETWEEN SEC. CORNERS; STONE 24X12X3; PINE N15W 288LKS.  
1973 ROWE; ROWE, P.S. #11192; SURVEY L.437 PG.345; NO OBJECT STATED; N15W, 97.90' TAG #11192 IN 4" POPLAR, N05E 72.20' TAG # 11192 IN 4" POPLAR, N60E, 101.18' TAG# 11192 IN P.POLE  
1975 ROWE; ROWE, P.S.#11192; LCRC PG. 16; DUG LARGE EXC., FND. NOTHING, SET 1/2" ROD IN C/L ELMWOOD RD. ON LINE WITH FENCE TO NORTH; SAME WITS AS 1973 SURVEY CITED ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, P.S.#37276; FND. 1/2" ROD; RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND. ROD IS IN SAME POSITION AS 1973 SURVEY CITED IN SECTION A. ABOVE

ACCEPTED FND. ROD AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
B-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED B13 T14N R10E IN MON. BOX  
N56°E, 101.10' FND. NAIL W/TAG #11192 IN SW FACE P.POLE  
S62°W, 32.67' SET 1/2" ROD W/CAP #37276  
S67°E, 35.04' SET 1/2" ROD W/CAP #37276  
N45°W, 43.81' SET P-K NAIL W/ TAG #37276 IN S. FACE 4X4 POST

Signed by *Jonathan M. Field* Date 10-7-97  
Surveyor's Michigan License No. 37276



APPROVED  
*[Signature]*  
10-6-97

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, MAY 14, 1975  
ADAPTED FROM BOARD'S PROCEEDINGS MARCH, 1983

SURVEY &  
REMONUMENTATION

NOV 26 1997

COMMISSION

