

COPY

1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILE NO. #40  
ELMWOOD TOWNSHIP  
97 OCT -9 PM 1:07

For corners in: ELMWOOD TWP.

<u>TUSCOLA</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>10E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Christina M. ...*  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JULY 25 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1835 GLO; PARKE, D.S.; SET POST; ELM 18 N67 1/2E 31LKS., LYNN 9 N42W 15 1/2LKS.  
1891 FELTON, C.S.; SURVEY OF SEC. 34; PREV. SET CEDAR POST AND CROCKERY; ELM 6 N69E 116LKS.  
1972 ROWE; ROWE, P.S. #11192; SURVEY L.1 PG.522-523; 1" ROD IN MON. BOX; WEST 25.80' NW COR. SEC. 3 T13N-R10E, N70W 74.50' TAG IN P.POLE, N40E 70.27' TAG IN P.POLE, S45E 62.24' NAIL IN P.POLE., W 9.7' C/L ROAD  
1973 ROWE, P.S. #11192; LCRC PG.10; 1" ROD IN MON. BOX; SAME WITS AS 1972 SURVEY CITED ABOVE  
1979 CASE SURVEYING; CASE, P.S. #15399; SURVEY L.500 PG.913; FND. 3/4" PIN IN MON BOX; S45W 46.7' 1/2" STEEL PIN, S55E 62.6' NAIL IN SW SIDE T.POLE, N45E 70.35' NAIL IN SE SIDE P.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, P.S.#37276; FND. 3/4" ROD IN MON. BOX; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1972 SURVEY CITED IN SECTION A ABOVE

ACCEPTED FND. ROD AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-13 RAISED FND ROD W/ 5/8" ROD&STD. REMON. CAP STAMPED G 13 T14N R10E IN MON. BOX ENCASED ROD WEST, 25.81' FND. 5/8" ROD IN MON. BOX APPARENT CORNER G-1 T13N-R10E & CAP IN CONC.  
N40°E, 70.23' SET P-K NAIL W/TAG #37276 IN NW FACE P.POLE  
S59°E, 62.43' SET P-K NAIL W/TAG #37276 IN SW FACE T.POLE  
N55°W, 39.30' SET 1/2" ROD W/CAP #37276  
S47°W, 43.27' SET 1/2" ROD W/CAP #37276

Signed by Jonathan M. Field Date 9-30-97  
Surveyor's Michigan License No. 37276



APPROVED  
9-29-97

*Handwritten signature/initials*

SURVEY &  
REMONUMENTATION

NOV 26 1997

COMMISSION

