

copy

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

LINDER NO. _____ PAGE NO. _____

FILE # #42
ELMWOOD TOWNSHIP
97 OCT -9 PM 1:07

For corners in: ELMWOOD TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>10E</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 25 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1835 GLO; PARKE, D.S.; SET POST; BEECH 16 N49W 38LKS., BEECH 16 N69E 57 1/2LKS.
1891 FELTON, C.S.; SURVEY OF SEC. 34; SET FROM MEAS. (NO OBJECT STATED); SUGAR 4 N30 3/4E 59LKS., ELM 10 S68 1/2W 116LKS.
1976 TOMMER; LCRC PG.14; FND. NOTHING; SET ON LINE & EQUIDISTANT FROM G-13 TO H-13 BASED ON 1891 RESURVEY; WEST 17.54' T-IRON, S45E 65.05' FACE OF P.POLE, S70W 69.75' TOP OF TEL. RISER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, P.S.#37276; FND. T-IRON; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. T-IRON IS IN SAME POSITION AS 1976 LCRC CITED IN SECTION A ABOVE

ACCEPTED FND. T-IRON AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-13 REPLACED FND. T-IRON W/ STD. REMON. MONUMENT STAMPED I-13 T14N R10E IN MON. BOX
WEST, 17.62' FND. T-IRON APPARENT CORNER I-1 T13N-R10E
S35°E, 65.12' FND. NAIL W/TAG #11192 IN SW FACE P.POLE
S64°W, 70.13' TOP CENTER OF PHONE RISER
N60°W, 35.71' SET 1/2" ROD W/CAP #37276
S50°W, 43.00' SET 1/2" ROD W/CAP #37276
N38°E, 24.97' SET 1/2" ROD W/CAP #37276

Signed by Jonathan M. Field Date 9-30-97
Surveyor's Michigan License No. 37276



APPROVED
9-29-97
[Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY &
REMONUMENTATION

NOV 26 1997

COMMISSION

