

COPY

1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

RECEIVED FOR RECORD

LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_

FILE NO. # 44

Filing Requirement of Act 74, Mich. P.A. 1970

ELMWOOD TOWNSHIP

97 OCT -9 PM 1:07

For corners in: ELMWOOD TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>10E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Jonathan M. Field*

TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JULY 25 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1835 GLO; PARKE, D.S.; SET POST; BIRCH 10 N81W 3LKS., CEDAR 7 N69E 1LK.  
1979 QUIST; LCRC PG.23; FND. T-IRON; EAST 11.88' FND. T-IRON AT NW COR. SEC.1, S60W 100.33' SPIKE IN P.POLE, S70E 85.30' TAG #11192 IN T.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, P.S.#37276; FND. T-IRON; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. T-IRON IS IN SAME POSITION AS 1979 LCRC CITED IN SECTION A ABOVE ; ALSO FND. LARGE STONES BELOW FND. T-IRON

ACCEPTED FND. T-IRON AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-13 REPLACED FND. T-IRON W/ STD. REMON. MONUMENT STAMPED K 13 T14N R10E IN MON. BOX  
EAST, 11.89' FND. T-IRON APPARENT CORNER K-1 T13N-R10E  
S74°E, 85.46' SET P-K NAIL W/TAG #37276 IN TDP CENTER OF CUT-OFF T.POLE  
N14°E, 97.85' SET P-K NAIL W/TAG #37276 IN SE FACE T.POLE  
S61°W, 100.38' SET P-K NAIL W/TAG 37276 IN NW FACE P.POLE  
S32°E, 36.05' SET PUNCH HOLE IN BOLT TOP SE END ARCH CULVERT  
N46°W, 32.64' SET PUNCH HOLE IN BOLT TOP NW END ARCH CULVERT



Signed by *Jonathan M. Field*  
Surveyor's Michigan License No. 37276

Date 9-30-97

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1993  
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED  
9-29-97

*Handwritten initials: JMF, RRB*

SURVEY &  
REMONUMENTATION

NOV 26 1997

COMMISSION

