

SURVEY & REMONUMENTATION

MAR 02 1999

**1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in: **ELMWOOD TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>10E</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 15 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. #54
FILE NO. ELMWOOD TWP
98 NOV 20 AM 11:40

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:
1835 GLO; PARKE D.S.; SET 1/4 SEC. POST; SUGAR 22 N24 1/2W 16 1/2 LKS., BEECH 11 S28W 30 LKS.
1987 HURON SURVEYING INC.; BROWN, P.S.#24588; SURVEY L.572 PG.330; FND 1/2" RE-ROD; EAST 42.18' NAIL S SIDE P/P, WEST 30.0' NAIL S SIDE 6" ELM, NORTH 47.65' NAIL S SIDE 10" APPLE

GLO NOTES FOR T14N-R11E IMPLY THAT THIS CORNER IS COMMON WITH A-12 T14N-R11E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998 ROWE; FIELD, PS #37276; FND. 1/2" ROD ON C/L GRAVEL ROAD N-S; RECOVERED 3 PREVIOUS WITS. WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1987 SURVEY CITED IN SECTION A. ABOVE.

ACCEPTED FND. ROD AS A CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-12 REPLACED FND. 1/2" ROD W/ STD. REMON. MONUMENT & CAP STAMPED M 12 T14N R10E
WEST, 29.92' SET NAIL W/ TAG #37276 IN S. FACE 8" ELM
S85°E, 42.10' FND. NAIL W/ FLAG. IN S. FACE P. POLE
N25°W, 47.58' FND. NAIL W/ FLAG. IN S. FACE 12" APPLE
N20°E, 79.51' SET NAIL W/ TAG #37276 IN E. FACE 8" ELM



Signed by Jonathan M. Field Date 11-2-98
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN SURVEYORS BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY & REMONUMENTATION

APPROVED
10-12-98
13100
THE
RAB

MAR 02 1999

SECTION



L-13
1997 REMON
PG. 45

M-13
1997 REMON
PG. 46

90°12'18" 2635.45' ROWE '98
2636.67' R.S. SCOTT '75
1835 GLO 2640'

M-12
180°08'24"

2630.01' ROWE '98
2631.23 R.S. SCOTT '75
1835 GLO 2640'

M-11
180°02'08"

CASS CITY ROAD (M-81)

ELMWOOD ROAD

DODGE ROAD

SEC. 36
T14N-R10E

SEC. 31
T14N-R11E