

SURVEY & REMONUMENTATION

MAR 02 1999

SECTION

**1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 55
FILE NO. ELKLAND TWP.

98 DEC -1 AM 8:57

Jon M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in: **ELKLAND TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>11E</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD in a field survey on MAY 15 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1835 GLO; PARKE D.S.; SET AS M-11 T14N-R10E; POST; HEMLOCK 22 S65W 12 LKS., SUGAR 15 N5W 13 1/2 LKS. 1975 R.S. SCOTT FOR T.C.R.C.; DODGE ROAD PLANS ELMWOOD ROAD TO M-81; SET P-K NAIL; N35W 68.00' P.POLE

GLO NOTES FOR T14N-R11E INDICATE THAT THIS CORNER IS COMMON WITH M-11 T14N-R10E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998 ROWE; FIELD, PS #37276; FND. NO EVIDENCE OF MONUMENT AT CORNER POSITION; REESTABLISHED CORNER POSITION BY PROPORTION OF R.S. SCOTT DISTANCES BY STATIONING & EXTENDING LINE FROM M-12 T14N-R10E THROUGH FND. NAIL ON SEC. LINE (PER T.C.R.C.) 1346± N OF M-12. CORNER POSITION THUS REESTABLISHED FALLS ON C/L OF DODGE ROAD N-S & 0.7' S. OF C/L M-81 E-W.

ACCEPTED PROPORTION AS BEST REESTABLISHMENT OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-11 SET STD. REMON. MONUMENT & CAP STAMPED M 11 T14N R10E IN MON. BOX
N16°E, 60.22' SET P-K NAIL IN ASPH.
N32°W, 69.67' FND. NAIL W/ MSHD TAG IN P.POLE
N70°W, 167.98' FND. NAIL W/ MSHD TAG IN P.POLE
S71°W, 155.54' FND. NAIL W/ MSHD TAG IN 15" MAPLE
N60°E, 46.49' SET 1/2" ROD W/ CAP #37276
N40°E, 53.51' SET 1/2" ROD W/ CAP #37276



Signed by Jonathan M. Field Date 11-26-98
Surveyor's Michigan License No. 37276

APPROVED
10-19-98
[Signature]



SEC. 25
T14N-R10E

M-10

179°55'16"

A-10

DODGE ROAD

SEC. 30
T14N-R11E

2617.12' ROWE '98
2624.50' MDOT
1835 GLO 2640'

M-11

180°02'08"

A-11

CASS CITY ROAD (M-81)

SEC. 36
T14N-R10E

M-12

180°08'24"

A-12

DODGE ROAD

SEC. 31
T14N-R11E

2630.01' ROWE '98
2631.23 R.S. SCOTT '75
1835 GLO 2640'

SURVEY &
REMONUMENTATION

MAR 02 1999

SECTION