

COPY

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. #58
FILE NO. Elkland Twp.

99 DEC 20 AM 8:23

For corners in Elkland Twp.

| | | |
|---------------------------------------|----------------------------|---------------|
| <u>Tuscola</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>114N</u> R <u>11E</u> | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Gregory M. Lohela
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Lionel Roy Emery, in a field survey on July 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1835 GLO; PARKE, D.S.; SET POST; BEECH 9 N41W 24-1/2, HEMLOCK 10 N83E 30.
- 1971 ROWE, PS#11192; LCRC P.4; DUG FOR CORNER - FOUND NO EVIDENCE; SET T-IRON AS OCCUPIED IN CENTERLINE - CENTERLINE OF ROADS; N40E 95.22' NAIL & TAG IN PP, S12E 32.87' NAIL & CAP IN ANCHOR POST, N30W 37.55' RD. SIGN POST.
- 1973 ROWE, PS#11192; LCRC P. 8; DUG FOR CORNER FOUND NO EVIDENCE, SET T-IRON AS OCCUPIED; N40E 95.22' NAIL & TAG IN ANCHOR POST, S02E 32.87' NAIL & TAG IN ANCHOR POST, N30W 37.55' ROAD SIGN POST
- 1973 ROWE ENGINEERING; ROWE, PS#11192; SURVEY L. 437 P. 371-372; FOUND T-IRON; N40E 95.22' NAIL & TAG IN PP, S02E 32.89' NAIL & CAP IN ANCHOR POST, N30W 37.55' ROAD SIGN POST
- 1973 ROWE ENGINEERING; ROWE, PS #11192; SURVEY L. 436 P. 255-256; T-IRON NOTED BUT NOT INDICATED IF FOUND OR SET; N40E 95.22' NAIL & TAG IN PP, S02E 32.87' NAIL & CAP IN ANCHOR POST, N30W 37.55' ROAD SIGN POST

(CONTINUED OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999 EMERY, PS#24593; FOUND T-IRON; RECOVERED 3 PREVIOUS ACCESSORIES WHICH INDICATE THAT FOUND T-IRON IS IN SAME POSITION AS ROWE SURVEYS CITED ABOVE.

ACCEPTED FOUND T- IRON AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13
SET STD. REMON. MONUMENT STAMPED K 13, T14N R11E
N40°E, 95.96', SET REMON. TAG IN SE FACE OF UTILITY POLE ABOVE FOUND NAIL
S50°E, 62.70', FACE OF STEEL PIPE ROAD SIGN POST
S02°E, 32.74', SET REMON. TAG IN N. FACE OF WOOD POST ABOVE FOUND NAIL
N25°W, 34.16', E. EDGE OF YIELD SIGN POST



DUE TO THE UNTIMELY ILLNESS OF MR. LIONEL ROY EMERY, I, KARI M. LOHELA, HAVE REVIEWED HIS FIELD NOTES AND PREPARED THIS FORM FOR PEER GROUP REVIEW

Signed by Kari M. Lohela
Surveyor's Michigan License No. 44289

Date 12/15/99

APPROVED MLL
12-15-99 RUB
gmg

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995

(PART A CONTINUED)

- 1976 ROWE ENGINEERING; FOKENS, PS#21567; SURVEY L. 464 P. 504-505; T-IRON NOTED BUT NOT INDICATED IF FOUND OR SET; N40E 95.20' NAIL & TAG IN PP, S02E 32.91' NAIL & CAP IN STUB OF TP, EAST 32.64' IRON W/CAP #11192, S60E 61.60' '4' ON RD. SIGN POST, N20W 31.35' YIELD SIGN POST
- 1988 DUNTON LAND SURVEYING; DUNTON, PS#23503; SURVEY L. 582 P. 967-968; NO INDICATION OF OBJECT OR ACCESSORIES.

