

COPY

1999 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. #57
FILE NO. Elkland Twp

99 DEC 20 AM 8:23

For corners in Elkland Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T14N R11E</u>	<u>L-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

[Signature]
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Lionel Roy Emery, in a field survey on July 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1835 GLO; PARKE, D.S.; SET POST; HEMLOCK 10 N46E 25, IRONWOOD 5 N45W 9-1/2.
- 1971 ROWE, PS#11192; LCRC P.2; FOUND STONE PILE & PIECES OF WOOD 3' BELOW ROAD; SET T-IRON; N50W 60.39' NAIL & CAP IN 12" MAPLE, N45E 43.39' NAIL & CAP IN 18" CATALPA, S15E 38.74' NAIL & CAP IN 18" CATALPA, S50W 63.85' NAIL & CAP IN T.P.
- 1971 ROWE ENGINEERING; ROWE, PS#11192; SURVEY L. 1 OF SURVEYS P. 286-287; T-IRON NOTED BUT NOT INDICATED IF FOUND OR SET; N45E 43.39' 18" CATALPA, S15E 38.74' 18" CATALPA, N50W 60.39' 12" MAPLE
- 1973 ROWE ENGINEERING; ROWE, PS#11192; SURVEY L. 437 P. 371-372; FOUND T-IRON; ACCESSORIES SAME AS IN 1971 ROWE SURVEY CITED ABOVE.
- 1973 ROWE ENGINEERING; ROWE, PS#11192; SURVEY L. 436 P. 255-256; FOUND T-IRON; ACCESSORIES SAME AS IN 1971 ROWE SURVEY CITED ABOVE.

(CONTINUED OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999 EMERY, PS#24593; FOUND 1" PIPE OVER T-IRON; RECOVERED 2 PREVIOUS ACCESSORIES FROM 1975 CASE SURVEY, AND 2 ACCESSORIES FROM 1974 ROWE SURVEY, WHICH INDICATE THAT FOUND 1" PIPE IS IN SAME POSITION AS THOSE SURVEYS CITED ABOVE; ENCOUNTERED A BED OF (6) 4" TO 6" STONES AT DEPTH OF APPROX. 2.5'.

ACCEPTED FOUND 1" PIPE AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13
SET STD. REMON. MONUMENT STAMPED L13, T14N R11E
N50°E, 46.05', FACE OF STEEL PIPE ROAD SIGN POST
S20°E, 39.02', SET REMON. TAG IN W. FACE OF 26" CATALPA
S70°W, 64.04', SET REMON. TAG IN SE FACE OF UTILITY POLE
N50°W, 60.67', SET REMON. TAG IN NE FACE OF 24" MAPLE ABOVE FOUND NAIL



DUE TO THE UNTIMELY ILLNESS OF MR. LIONEL ROY EMERY, I, KARI M. LOHELA, HAVE REVIEWED HIS FIELD NOTES AND PREPARED THIS FORM FOR PEER GROUP REVIEW

Signed by *Kari M. Lohela* Date 12/15/99
Surveyor's Michigan License No. 44289

APPROVED 1300
12-15-99 RUB
gmg

(PART A CONTINUED)

- 1975 CASE SURVEYING; CASE, PS#15399; SURVEY L. 451 P. 997; FOUND T-IRON, N55E 44.1' SPIKE IN SE SIDE OF 20" MAPLE, N60W 60.9' SPIKE IN NW SIDE OF 15" MAPLE, SOUTH 18.85' W. EDGE OF TRAFFIC DIRECTIONAL SIGN
- 1976 ROWE ENGINEERING; FOKENS, PS #21567; SURVEY L. 464 P. 504-505; NO INDICATION OF OBJECT OR ACCESSORIES

