

DEC 07 1994

COMMISSIONER

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ELKLAND TOWNSHIP

<u>TUSCOLA</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>14N</u> R <u>11E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 32
ELKLAND TWP.
94 NOV -9 PM 2: 15

VIRGINIA M. McLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Lionel Roy Emery, in a field survey on July 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1835 (Gov't. Land Office Notes) Harvey Parke, D.S. -Township corner established- Hemlock 24 N65E 31; Hemlock 28 S48W 59.

1888 (County Surveyor's Record, pages 80 and 81, Tuscola County) John A. Teskey, County Surveyor -Stake previously established- Perpetuated by Stone.

1976 (Survey -Liber 466, page 834, Sanilac County) Stewart G. Case, P.S. 15399 -Fd. circle of rocks in place. placed 1/2" steel pin in middle of rocks.- Spike in SW side of T.P., S45°E - 58.2'; Spike in NW side of T.P., S45°W - 48.4'; Center of enter Huron Co. sign, N25°E -60.85'

1978 (Survey -Liber 4 of Surveys, pages 198 and 199, Sanilac County) Stewart G. Case, P.S. 15399 Fd. 1/2" iron in place. ---See over for continuation of Section A.---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" diameter 24" long reinforcing rod in middle of pile of fieldstones 15"+/- below surface of gravel road. Stones were 6"-10" diameter and in layer 18"+/- deep.

Accepted found iron and stone pile as marking original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed found iron and cleared enough stones to replaced iron with Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M1 T14N/R11E
N20°E, 46.04' -set 1/2" diameter reinforcing rod.
N22°E, 61.6' -Center of "Enter Huron County" sign.
S15°E, 94.70' -T.C. Re-mon. tag in West face of 18" Mulberry tree.
S45°W, 48.40' -T.C. Re-mon. tag in Northwest face of Telephone Pole.
N15°W, 50.70' -set 1/2" diameter reinforcing rod.



Signed by Lionel Roy Emery

Date Oct. 24, 1994

Surveyor's Michigan License No. 24593

APPROVED
10-24-94
[Signature]

9.00

Spike NW side T.P., S50°W-48.38'.; Spike SW side T.P., S45°E-58.16'.; Steel sign post, N20°E-60.85'.

COPY

