

DEC 23 2000

COPY

SECTION

RECEIVED FOR RECORD

LIBER NO. _____ PAGE NO. _____

1994 REMONUMENTATION PROGRAM FILING NO. #33
LAND CORNER RECORDATION CERTIFICATE ELKLAND TWP.

Filing Requirement of Act 74, Mich. P.A. 1970 94 NOV -9 PM 2:15

For corners in ELKLAND TOWNSHIP

VIRGINIA M. McLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

TUSCOLA (County)	Located In:	Corner Code #/
1. Public Land Survey	T 14N R 11E	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Lionel Roy Emery, in a field survey on July 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1835 (Gov't. Land Office Notes) Harvey Parke, D.S. -Set qr. Sec. post- Birch 15 S5W 44; B. Ash 10 N34W 15 1/2
- 1888 (County Surveyor's Record, pages 80 and 81, Tuscola County) John A. Teskey, County Surveyor -Established equal distance between Sec. corner- Perpetuated by: Pine S45W. --No additional accessories given. (Note: Plat shows corner was not re-established at 'equal distance' between Section corners.)
- 1976 (Survey -Liber 466, Page 834, Tuscola County) Stewart G. Case, P.S. 15399 -Fd. Cedar stake in place, raised with 5/8" steel pin- 1/2" iron pin, W. - 30.0'; 1/2" iron pin, E. - 26.0'; Spike in E. side of P.P., N50°E - 71.25'

---See over for continuation of Section A.---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 5/8" diameter 27" long reinforcing rod in centerline of gravel road at fence line to East.

Accepted found rod as marking original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Removed found iron and replaced with Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M2 T14N/R11E.
- N50°E, 71.16' -T.C. Re-mon. tag above found nail in Northwest face of Power Pole.
- S80°E, 26.00' -Found 1/2" diameter reinforcing rod.
- S80°E, 22.39' -T.C. Re-mon. tag in South face of 12" Stump.
- S40°W, 17.70' -Set 1/2" reinforcing rod.
- N34°W, 19.51' -Set 1/2" reinforcing rod.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Lionel Roy Emery
Surveyor's Michigan License No. 24593

Date Oct. 24, 1994

APPROVED

10-24-94



1978 (Survey -Liber 4 of Surveys, pages 198 and 199, Sanilac County) Stewart G. Case, P.S. 15399
 -Fd. 1/2" iron pin in place.- Spike S. side 14" Ash T., stump, East-28.3'; Spike SE side 6" Ash T., S40°W-44.6'.; Spike NW side P.P., N50°E-71.6'.

COPY

