

SURVEY &
MONUMENTATION

REC 43 2000

SECTION

RECEIVED FOR RECORD

LIBER NO. _____ PAGE NO. _____

1994 REMONUMENTATION PROGRAM FILING NO. #34
LAND CORNER RECORDATION CERTIFICATE EIKLAND TWP.
Filing Requirement of Act 74, Mich. P.A. 1978 04 NOV -9 PM 2:15

For corners in ELKLAND TOWNSHIP

VIRGINIA M. McLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

TUSCOLA (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>14N</u> R <u>11E</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Lionel Roy Emery, in a field survey on July 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1835 (Gov't. Land Office Notes) Harvey Parke, D.S. -Set post corner Secs. 1 & 12 Hemlock 12 N12W 21; Hemlock 6 SW 25
1888 (County Surveyor's Record, pages 80 and 81, Tuscola County) John A. Teskey, County Surveyor -Stake previously established- no accessories given.
1977 (Survey -Liber 475, page 336, Tuscola County) Stewart G. Case, P.S. 15399 -Pd. 1/2" iron pin in place- spike NW side P.P., N50°E-75.31, spike in SE side T.P. -S45°W-45.12', center of steel Rd. sign post-N45°W-41.65',

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" diameter 15" long smooth rod in monument box.

Accepted found rod as marking original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Removed 3/4" diameter rod and replaced with 5/8" diameter 15" long reinforcing rod with 2" Brass Cap stamped M3 T14N/R11E. Rod and cap set in concrete in monument box.
N50°E, 75.18'-T.C. Re-mon. tag in Northwest face of Power Pole.
S26°E, 38.43'-T.C. Re-mon. tag in Southwest face of 60" Box Elder.
S45°W, 45.08'-T.C. Re-mon. tag above found nail in Southeast face of Telephone Pole stub.
N40°W, 37.15'-Exposed 3/4" diameter iron in top of leaning triangular concrete marker.

Signed by Lionel Roy Emery


Date Oct. 24, 1994

Surveyor's Michigan License No. 24593

APPROVED

10-24-94


FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 11, 1975
REVISED JAN., 1983



7.00

COPY

TUSCOLA COUNTY
ELKLAND TWP.
T14N-R11E



NO SCALE

