

COPY

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ELKLAND TOWNSHIP

<u>TUSCOLA</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T 14N R 11E	M-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 11
ELKLAND TWP
94 NOV -9 PM 2:16
VIRGINIA M. McCLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Lionel Roy Emery, in a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1835 (Gov't. Land Office Notes) Harvey Parke, D.S. -set qr. Sec. post- Beech 12 S8W 43; Sugar 8 N50W 6
 1973 (Survey -Liber 431, page 188, Tuscola County) Stewart G. Case, P.S. 15399 - Found pointed stone in middle of nest of stones. Measures 1320.0 feet East of established East 1/8 line. Spike in NW side of T.P., S55°W -47.37'; Spike in SE side of P.P., N45°E -38.02'; Middle of road sign post, N35°W -50.75' -No indication of placement of additional marker to perpetuate corner position.
 1978 (Survey -Liber 489, pages 980 and 981, Tuscola County) Stewart G. Case, P.S. 15399 -same corner marking and accessories as previously noted Survey-
 1978 (Survey -Liber 492, pages 546 and 547, Tuscola County) ---See over for continuation---
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1" inside diameter 9" long pipe over 1/2" reinforcing rod 12" long in middle of group of stones at centerline/centerline intersection of "Greenland" Road North-South and "Walker" Road to West. Distance check to Northeast corner of Section 25 is substantially the same as noted on Case's Surveys. One remaining accessory also checks.

Position of found marker not accepted as marking original corner. Position reestablished after reviewing aerial (1941) photos and other records showing Walker Road as Drive to NW 1/4 of SE 1/4. Reestablished position of corner at single proportion measure. This position appears to be close to the average 1/2 mile measurements along the East line of Tuscola County.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M10 T14N/R11E.
 N25°E, 62.41' -T.C. Remon. tag in Southeast face of Power pole
 S60°E, 50.51' -T.C. Remon. tag in Southwest face of 10" Apple tree
 West, 13'+/- -Centerline of Gravel Road North-South
 N82°W, 47.01' -T.C. Remon. tag in North face of Tele pole stub
 N24°W, 89.88' -T.C. Remon. tag in Northeast face of 5" Ash in clump



Signed by Lionel Roy Emery Date Nov. 7, 1994
 Surveyor's Michigan License No. 24593

APPROVED
11-7-94

-same corner marking and accessories as previously noted Survey-
1978 (Survey -Liber 492, pages 552 and 553, Tuscola County) Stewart G. Case, P.S. 15399 -same
corner marking and accessories as previously noted Surveys.

COPY

