

DEC 07 1994

1994 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in ELKLAND TOWNSHIP

TUSCOLA  
(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 14N R 11E M-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
LIBERNO... PAGE NO...  
FILINGS NO. #43  
ELKLAND TWP  
94 NOV -9 PM 2:16  
VIRGINIA M. McLAREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS

**COPY**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Lionel Roy Emery, in a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1835 (Gov't. Land Office Notes) Harvey Parke, D.S. -Set qr Sec. post- Pine 50 N35W 35½; Sugar 5 S53W 12  
No record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of corner marker found.

Reestablished corner position in East line of Section 36, T14N-R11E at fence occupation East into Section 31, T14N-R12E. No occupation appears to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Placed Standard Tuscola County Concrete Monument with 2" Brass Cap stamped M12 T14N/R11E  
N86°E, 23.15' -T.C. Re-mon. tag in South face of 6 x 6 Tele Pedestal support post.  
S06°E, 25.32' -set ½" reinforcing rod.  
S44°W, 85.86' -T.C. Re-mon. tag in Northwest face of Power Pole.  
N35°W, 34.74' -set ½" reinforcing rod.

Signed by Lionel Roy Emery

Date Oct. 20, 1994

Surveyor's Michigan License No. 24593

**APPROVED**  
10-20-94  
*[Signature]*



COPY

