

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>22</u> T. <u>15</u> N. R. <u>8</u> E.		<u>G-9, I-8</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

87

I, Thomas G. Moran, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-9 This corner was recovered and used in a survey by G. B. Felton in September 6-8, 1902. The corner was cedar post and stone.
- I-8 This corner was recovered and used in a survey by G. B. Felton in September 4-9, 1905. The corner recovered was a cedar post with crockery around it.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-9 Dug 10'x 12'x 4' hole in road intersection and found nothing. Set 4"x 36" concrete monument with aluminum cap. Corner set by single proportionate measure N-S and a ratio of Felton's measurement from the east.
- I-8 Dug and recovered old cedar post with crockery and glass around it. Set 4"x 36" concrete monument 6" below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>G-9 4"x 36" Concrete Monument.
S 55° W 19.06' N. most corner of N.W. wingwall
S 67° E 38.48' N. most corner of N.E. wingwall
N 40° E 19.2' Road intersection
S 14° W 74.40' N.E. corner pumphouse</p> | <p>I-8 4"x 36" Concrete Monument
N 20° W 48.87' 32" Cottonwood
N 77° E 8.60' N. most corner N.W. end of wingwall
S 12° E 38.8' W. most corner of S.W. end of wingwall
S 65° W 79.91' Power Pole</p> |
|--|---|


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Thomas G. Moran DATE 1-15-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 25860