

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

57

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>27</u> T. <u>15</u> N. R. <u>8</u> E.		<u>G-11, G-5</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ S., R. _____ W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S., R. _____ W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Thomas G. Moran, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-11 This corner was recovered and used in a survey by D. E. Craston January 27, 1870. Corner was recorded and iron rod placed by R. Black date unknown.
- G-5 This corner was recovered by R. Black. Iron rod placed over wooden post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-11 Recovered iron rod placed 1" iron pipe with plastic cap 6" below gravel surface.
- G-5 Dug and found iron rod set on top of wooden post set 1"x 36" iron pipe with plastic cap 6" below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| G-11 1" iron pipe.
N 45° W 87.39' Power Pole
N 45° E 88.04' Power Pole
S 33° W 66.50' N.E. Cor.
brick pumphouse
West 12.0' ⊥ N-S Road | G-5 1"x 36" iron pipe.
North 139.09' 8" Ash
N 66° E 47.90' 4" Ash
S 14° W 68.50' 4" Ash
East 13.0' ⊥ Gravel Road |
|--|--|

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Thomas G. Moran DATE 1-15-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 25860