

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in N. Akron Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> N R <u>8</u> E	<u>E-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton in a field survey on June 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1821 Joseph Wampler, D.S. Set post cor. Secs. 32 & 33 W. Oak 9 N 52 1/2 W 412 No other.	Dec. 10, 1869 Survey of Sec. 32, T15N-R8E D. E. Cranston, County Surveyor. No mention of object found or set or accessories. Dec. 26 to 31, 1901 Survey of Sec. 33, T15N-R8E by G. B. Felton, County Surveyor. Set from B.T.'s post at corner.
--	---

Note: Section A continued on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found nothing. Re-established corner proportional to 1901 resurvey of Section 33 by G. B. Felton.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard monument stamped Corner E-13, T15N-R8E. Placed monument box over monument.
S72°E 27.60' SW corner conc. bridge deck (36.6' x 24').
N44°E 38.65' NW corner conc. bridge deck (36.6' x 24').
S58°E 69.75' set T. C. Remon. tag & spike in NE face P. Pole.
N28°W 94.21' set T.C. Remon. tag & spike in SW face P. Pole.
N34°E 99.46' set T.C. Remon. tag & spike in SE face P. Pole.
S88°32'E 15.14' fnd. 1/2" rod in mon. box Apparent E-1, T15N-R8E
North 10'± physical centerline E-W asphalt pavement.
East 35'± centerline of Walker-Hayes Drain to North (not centerline Bridge).

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date 12-9-96

APPROVED
12-9-96 P.P.E.
JMT.
One



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT., 1985

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 46
SERIAL NO. N. Akron Twp.
SS ECD 25 PM 3:39

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

June 26, 1913 Minutes of Survey of the Walker and Hayes Drain, Book 20 on Pages 430 & 431 of the County Drain Records. No mention of objects found or set or accessories. The notes indicate that the drain crosses the South line of section, 32 feet East of the SW corner of the W 1/2 of the SW 1/4 of Section 33.

May 20, 1978 Survey by Earl E. Gravlin, RLS #23510, Liber 488-Page 547.
 N45°W 102.6' tag in Power Pole.
 S70°E 14.3' cor. bridge rail post.
 N20°E 31.01' cor. bridge rail post.
 North 10.00' centerline Bay Park Rd.
 West 14.00' centerline Thomas Rd.

April 23, 1979 Survey by Earl E. Gravlin, RLS #23510, Liber 496-Page 1491.
 Found 1/2" iron. Same accessories as L-488, P-547.

