

SURVEY & REMONUMENTATION

VAN BUREN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED

JAN 14 1998

For corners in

SECTION

Van Buren
(County)

Located In: Bloomingdale Twp.

Corner Code # C-1

- 1. Public Land Survey T 1 S R 14W
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S 5 T 1S R 14W
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

For C-1

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-1 GLO set post April 7 th 1830 28" Beech S 11°W 10 links Robert Clark Jr. no tie distance shown to Allegan County corner	C-1 County Survey Notes (W.H. Goss) Sept. 11, 1919; Book 7, P.218 Fd. Pipe with stones 5" Walnut S60-1/4°E 88-1/4 links 14" Sugar N62-1/2°E 125 links 3" Sugar S41-1/4°W 66 links	C-1 LCRC (Rec.L3, P. 85) Sept. 10, 1984 Found 1-1/4" pipe 1.5' S. of C.L. gravel road 2' West of road to south 36" Maple S 32°W 55.38' Road sign S 53°E 55.70' Dist. Pole N 21°W 25.95' Pine N 58°E 63.70'
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1-1/2" (o.d.) pipe 0.8' below surface of pavement. Witnesses from 1919 survey not found. Fits Witnesses recorded L3, P. 85.
 Excavated around pipe to a depth of 1.5' below road surface and found several large stones (4 "5" in diameter) laying in a ring next to pipe.
 And is accepted as a careful and faithful reestablishment of the position of the original closing corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-1 Slim line Harrison Marker in monument box.
 Harrison Marker is 1.73' south of town line as established by D-13 and E-13 on the south line of Cheshire Township, Allegan County. C-1 is 1149.28 feet westerly of E-13.
 Set PK nail and Van Buren County witness tag 0.6' above grade in NW side 18" Scotch Pine N 57°E 63.59 ft
 Set PK and Van Buren County witness tag 1.0' above grade in SW side Post for Telephone Pedestal S 65°E 71.15 ft
 Set PK nail and Van Buren County witness tag 0.8' above grade in E side in 36" Maple S 41°W 55.43ft
 Set PK nail and Van Buren County witness tag 0.8' above grade in SW side in Power Pole N 21°W 25.74ft
 Marker is at the intersection of the centerlines of Baseline Road and 44th Street.

Signed by Robert E. Lemke
 For SDI CONSULTANTS, LTD.

Date: December 03, 1997

Surveyor's Michigan License No. 40160

Ratified by Peer Group in
 accordance with P.A. 345 of 1990
 Van Buren County Surveyor

Date D. R. G. 12/26/97

DEC 26 10 56 AM '97

Mark A. Smith
 VAN BUREN CO.
 REGISTERED SURVEYOR

Liber 5 Page 99
 Register of Deeds Stamp & File
 Number

7-00
 12/26 0101 103 SURVEY