

**SURVEY & REMONUMENTATION**

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
Dec 26 10 50 AM '97

FILED

For corners in **SECTION**

Van Buren Located In: Bloomingtondale Twp. Corner Code #D-1  
(County)

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS

7-00

1. Public Land Survey	T	1	S	R	14	W	N1/4, sec. 5
	T		R				
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

D-1

*Liber 5 Page 98*

Register of Deeds Stamp & File Number

12/26 0101 10SURVEY

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Lemke, in a field survey on August 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	10			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>D-1 GLO</b>	<b>D-1 County survey Notes</b>	<b>D-1 Witness Card</b>	<b>D-1 LCRC</b>
not set	Book 7, page 218-established corner set tile around pipe. Sept. 11, 1919	3/4" iron	L. 3, P.85; 9/10/84
	12" Apple S.20°W. 59 links	26" Maple N55°E 50.26'	Fd. 1-1/4" pipe
	12" Apple S.52°W. 89.5 links	Fen Cor. & Iron N30°W 40.40'	10" Elm N46°E 31.79'
	W. H. Goss	Fen Line to N. 21.70'	Tel Pole S37°W 30.93'
		Old Fen Line to S. on Line	6" Elm South 26.12'
			12" Box Elder N67°W 50.61'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" (o.d.) pipe 0.5' below bituminous road. None of the witnesses from L. 3, P.85 remained. Witnesses from witness card are gone except for the south running fence which is 3' +/- west of pipe. Excavated 2.3' below surface of road and found no evidence of tile. 1919 survey by Goss established corner on the split of a mile that measured 5270.76' (1/2 mile = 2635.38'). By current measure D-1 is 2635.16' easterly of C-1 and is 2630.59' westerly of E-1. I believe this pipe to have been set in error. Set D-1 equidistant between C-1 and E-1 (1/2 mile = 2632.88 ft) and on the town-line as established by E-13 and F-13 on south line of Cheshire Twp, Allegan County.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**D-1 Slim line Harrison Marker in monument box.**  
Distance easterly to F-13 of Cheshire Twp (T. 1 N., R. 14 W) is 1132.28 ft.  
V-notch in center of the N. end of a 12" corrugated metal pipe N 45°W 51.00 ft  
V-notch in center of the S. end of a 12" corrugated metal pipe S 55°W 38.55 ft  
Set PK nail and Van Buren County witness tag in W side of a power pole S 25°W 28.91 ft  
Set 1/2" iron with cap #40160 at N edge of bit N50°E 23.67 ft  
Marker is 2' south of centerline of Baseline Road and is on an extension north of the old fence running south..

Signed by Robert E. Lemke  
For SDI Consultants, Ltd.

Date December 03, 1997

Surveyor's Michigan License No. 40160

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor  
Date D. R. G. 12/26/97