

SURVEY & REMONUMENTATION

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

DEC 26 10 56 AM '97

For corners in SECTION

Van Buren (County) Located In: Bloomingtondale Twp. Corner Code # E-1

- 1. Public Land Survey T 1 S R 14W
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S 5 T 1 S R 14W
S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

E-1 pm

For E-1

Mark A. Smith
VAN BUREN CO. REGISTERED SURVEYOR
7-00
7865 12/26 0101 10SURVEY
Like 5 Page 97
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|-------------------------------------|--------------------------------|---|
| E-1 GLO | E-1 County Survey Notes | E-1 LCRC (L.3, P.85) |
| Set post April 7 th 1830 | Book 7, Page 218 1919 | 1984 Ed McCombs set re-rod |
| 32" Whitewood S44°E 19 Links | Iron with Tile | 8" Elm N40°W 34.20 |
| 6" Beech S59°W 26 Links | 10" Sugar N31½°W 65½ Links | 24" Maple S65°W 50.84 |
| Robert Clark Jr. | 3" Walnut N42½°E 65 Links | 26" Maple S80°W 70.52 |
| | | 18" Walnut S20°W 64.77 |
| | | Spike & Witnesses from County Surveyor Office |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 0.8' below surface of pavement. The iron fits the witnesses per the 1984 LCRC. 1919 witnesses are gone. Excavated 3.5' below road surface and found no evidence of tile.

And is accepted as a careful and faithful **reestablishment** of the position of the original closing corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Slim line Harrison Marker in monument box.
 E-1 is 1121.91 ft westerly of G-13 (T 1 N, R 14 W) Allegan County, MI
 E-1 is on the Town-line as established by H-13 and G-13 of Cheshire Township (T 1 N, R 14 W).
 Set PK nail and Van Buren County witness tag 0.9' above grade in SE side 13" Maple N 55°E 42.49 ft
 Set PK nail and Van Buren County witness tag 1.0' above grade in SW side power pole(#V118-22) S 50°E 63.16 ft
 Set PK nail and Van Buren County witness tag in N side 30" Maple 1.3' above grade S 63°W 50.96ft
 Set PK nail and Van Buren County witness tag in NE side 48" Maple 1.3' above grade N 40°W 69.49ft

Ratified by Peer Group in accordance with P.A. 345 of 1990
 Van Buren County Surveyor
 Date D. R. L., 12/26/97

Signed by Robert E. Lemke
 FOR SDI CONSULTANTS, LTD.

Date 12/3/97

Surveyor's Michigan License No. 40160