

**SURVEY &
DEMONUMENTATION**

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bloomington Township
Van Buren County

(County)	Located In:	Corner Code #
	IS 14W	E-7
1. Public Land Survey	T ___ R ___	_____
SW Corner Sec. 16	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Maal & Smith
VAN BUREN CO.
REGISTER OF DEEDS

NOV 22 11 32 AM '95

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Gilchrist, in a field survey on October 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1830-Government - R. Clark, Jr., D.S. - North between Section 20 and 21 a distance of 80.00 chs. (5280.00') and set Post Corner. Witnesses: 14" Sugar Maple - S.75° East 31 lks. (20.46'), 20" Linden - N.75° West 19 lks. (12.54). 10/17/1866 - C.J. Monroe, C.S. - Section 16 Had Corner. 8/1870 A.J. Pierce, C.S. - Section 16. Corner set by C.J. Monroe, witnesses gone. Distance East of 39.87 chs. (2631.42') to South Quarter Post. 4/20/1903 W.H. Goss, C.S. Book 1 - Page 140 (Section 20) "Found corner well marked by stones, old leather, etc." 1961 Van Buren County Road Commission Spike & Tag, 40" Elm - SE - 42.0'; 16" Elm NE - 62.5'; 16" Elm - SW - 46.31'; DEF = 0°06' RT-STA 265 + 17.70 (3' of fill) (Continued on Reverse)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike in monument box - removed spike, Set Harrison Marker (slim line) in monument box. Approved at the May 3, 1995, Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date 5/3/95 D.R.G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set slimline Harrison Marker in monument box.
16" Walnut - S88° East 38.37' pk/w in East side
P.P. - North 20° East 68.94' - pk/w in West side
12" Elm - North 20° West 68.98' - pk/w in East side
CR 665 sign - South 40° West 26.86'
in centerline of road.



Liber 4 pg. 316

Signed by Donald R. Gilchrist Date 11/22/95
Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

3/31/1972 - W. Q. Smith, C.S. (D. Middleton, R.L.S.)

Section 17.

Recorded Survey (Liber 1 - Page 366).

Found Railroad Spike from 10/25/1970 witness.

Witnesses:

City Limit Sign - West Post is East - Northeast 20'.

Phone Pole 36' West to center line Spike in center line pavement.

Distance North of 2622.84' to Quarter Post.

Distance West is 2630.06' to Quarter Post.

8/19/1971 - Recordation Certificate (Liber 1 - Page 108) by D. Middleton, same as above.

2/27/1995 - D. R. Gilchrist, C.S.

Section 16.

Found Railroad Spike in Monument Box.

Survey shows distance East is 1317.76' to Eighth Post, and continues East 1317.76' to South Quarter Post for a total of 2635.52'.

Distance North is 2622.62' to West Quarter Post.

Liber 4 pg. 317