

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE  
 COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bloomington Township

Van Buren County Located In: \_\_\_\_\_ Corner Code # E-8  
 (County)

1. Public Land Survey	T <u>1S 14W</u>	_____
	T _____	_____
West 1/4 Post Sec. 21	T _____	_____
	T _____	_____
2. Property Controlling in Section	S _____	T _____
	S _____	T _____
3. Miscellaneous Property in Sec.	S _____	T _____
	S _____	T _____

*M. A. Smith*  
 VAN BUREN CO.  
 REGISTER OF DEEDS

NOV 22 11 32 AM '95

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald R. Gilchrist in a field survey on October 19 95, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1830 Government R. Clark, Jr. D.S. North between Sections 20 and 21 a distance of 40.00 chs. (2640.00') and set Quarter Post Witnesses: 8" Beech - S65° West 11 lks. (7.26'); 16" Sugar - N. 7° West 7 lks. (4.62').  
4/20/1903 W. H. Goss, C.S. "Found corner marked by stones". 4/1/1903 - Notes: Distance North is 40.065 chs. (2644.29') to Northeast Corner. 6/30/1923 - T.A. Smith C.S. County Highway Notes show a stone. 1961 Van Buren County Road Commission Fen line West at STA 238 + 80 ±. 6/12/1973 W.O. Smith, C.S. Section 21. Recorded Survey (Liber 3 - Page 323) shows corner. Set Iron in center of empty monument box.  
 4/18/1973 - Recordation Certificate (Liber 2 - Page 97) Same as above. 9/4/1973 - Recorded Survey (Liber 4 - Page 33) shows corner same as above. 10/30/1973 - Recorded Survey (Liber 4 - Page 198) shows corner same as above. Distance South is 2642.26'. 11/8/1973 - Recorded Survey in Sec. 20 (Liber 4 Page 197) shows corner same as above. Distance South 2642.26'. Distance West 2634.82' to center Quarter Post.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in monument box - dug 3' - did not hit a stone - set Harrison Marker (slimline) in monument box. Approved at the May 3, 1995, Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
 Van Buren County Surveyor

Date 5/13/95 *D.R.G.*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Slimline Harrison Marker in monument box.  
 P.P. N 24°30' East 89.90'  
 P.P. S 15°15' East - 136.13'  
 6" Ash - S 32° 30' West - 73.86'  
 12" Elm - North 82°30' West 43.45'  
 Centerline of North and South Road - East 1.5±

*Liber 4 Pg. 320*



Signed by Donald R. Gilchrist Date 11/22/95