

**SURVEY & REMONUMENTATION**

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

DEC 26 10 56 AM '97

**SECTION**

For corners in

Van Buren (County) Located In: Bloomingdale Twp. Corner Code # F-1

1. Public Land Survey T 1 S R 14W N1/4, sec. 4  
 T R  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

F-1

*Mark A. Smith*  
 VAN BUREN CO.  
 REGISTERED SURVEYOR

*Liber 5 Page 96*  
 Register of Deeds Stamp & File Number

7-00  
 7865 12/26 0101 108URVEY

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1						4							
2	6				5					3		2	1
3													
4	7								8	9	10	11	12
5													
6	18									15	14	13	
7													
8	19									20	21	22	23
9													
10	30									29	28	27	26
11													
12	31									32	33	34	35
13													

I, Robert E. Lemke, in a field survey on August 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 F-1 GLO  
 not set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 5/8" re-bar and cap at surface of road. Cap number is illegible. F-1 has been re-established on split of mile. Current measure from E-1 to F-1 is 2640.04' and F-1 to G-1 is 2640.58'. F-1 is 0.32' south of town line as established by G-13 and H-13 on the south line of Cheshire Twp (T 1 N, R 14 W), Allegan County, MI. As requested by Van Buren County peer group, I monumented the position of F-1 on the town line as established by G-13 and H-13 on the south line of Cheshire Twp and on an equal split (2640.31') of the distance between E-1 and G-1. Total distance between E-1 and G-1 is 5280.62'.

This position not established by original government surveyors. And is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 F-1 Slim line Harrison in Monument Box  
 Distance easterly to H-13 of Cheshire Township is 1110.66ft and is on the town line as established by G-13 and H-13 of Cheshire Twp (T 1 N, R 14 W), Allegan County, MI.  
 Set nail and Van Buren County witness tag 1' above grade in NW side of a 32" Maple S50°W 34.97ft  
 Set nail and Van Buren County witness tag 1' above grade in N side Power Pole (V118-39) S55°E 122.03ft  
 Measured to center of a 24" Ornamental Cherry S35°E 53.7ft  
 Set Iron Rod with cap LS#40160 at N Edge of Pavement N70°W 14.70ft  
 Set Iron Rod with cap LS#40160 at N Edge of Pavement N65°E 18.59ft

Signed by Robert E. Lemke  
 For SDI CONSULTANTS, LTD

Date 12/3/97

Surveyor's Michigan License No. 40160

Ratified by Peer Group in accordance with P.A. 345 of 1990  
 Van Buren County Surveyor  
 Date D.R.A. 12/26/97