

SURVEY & REMONUMENTATION

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

DEC 26 10 56 AM '97

For corners in **SECTION**

Van Buren Located In: Bloomingtondale Twp. Corner Code # G-1
(County)

1. Public Land Survey T 1 S R 14W G-1
T R
T R
T R
T R

2. Property Controlling S 3 T 1 S R 14W NW Cor. Sec. 3
in Section S T R
S T R

3. Miscellaneous S T R
Property in Sec. S T R

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

Liber 5 Page 95
Register of Deeds Stamp & File Number

7-00
12/26 0101 105URVEY

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 GLO set post April 7 th , 1830 11" Beech S 44° E 47 links 8" Beech S 18° W 33 links Robert Clark Jr. no tie distance shown	G-1 Ratekin Survey (Rec. L.2, P.175) 6-27-72; found pipe Nail P. Pole N 50° E 69.95 Street sign east 31.35' NE corner HSE S 45 W 110.10	G-1 Ratekin Survey Rec. L.6,P. 194-197 7-15-75 Same wits as L.2, P. 175	G-1 LCRC (Rec.L3, P. 77) 3/4" Iron Rod (6/21/83) Donald L Bissell #18655 East 44.41' 6" apple N 53° E 69.93' Power Pole S 45° W 47.66' base flag pole S 64° E 36.21' 4" Conc. Monument Section B states Fd. 3/4" iron from DA Ratekin Survey, put plastic cap on rod.
G-1 Witness Card (no date) N.E. Cor. (Fd. 1/2" iron pipe) in Cen. Li. of road west, 8' West of Cen. Li. road Phone pedestal ene 36.35' Power pole NE. 70.2 Phone pole SW 69.6'			

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron with cap(#18655) 0.7' below road surface. House tie from 1972 survey fits found iron. Fits remaining witness's to the 1983 LCRC. Distance westerly to H-13 of Cheshire is 1529.65'. Witness card shows distance to nearest foot to be 1530 feet. Pulled 3/4" iron and set Harrison Marker on top of old rod.

And is accepted as a careful and faithful **reestablishment** of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Slim Line Harrison in Monument Box is 7' W of CL 40TH and 3'S of Baseline rd
G-1 is 1145.03' West of I-13 (SW Corner, Section 34(in lake), Cheshire Township(T 1 S, R 14 W)) and G-1 is 3.01' South of the town line as established by E-13 and G-13 on south line of Cheshire Twp, Allegan County.
NE Cor House #0080 S55°W 110.25ft
Set Iron Rod with Cap LS #40160 at edge of pavement N45°W 32.73ft
Set PK and Van Buren County witness tag in South side of Power Pole #a10-1 40 1' above grade N55°E 69.84
Found Concrete Monument S60E 36.20ft
Set PK and Van Buren County witness tag in South side of 14" Apple 1.5' above grade S65°E 44.27'

Signed by Robert E Lemke Date 12/3/97
FOR SDI CONSULTANTS, LTD.

Surveyor's Michigan License No. 40160