

SURVEY & REMONUMENTATION

JAN 14 1998

VAN BUREN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

FILED

DEC 26 10 56 AM '97

SECTION

For corners in

Van Buren (County) Located In: Bloomingdale Twp. Corner Code # I-1
1. Public Land Survey T 1 S R 14W NE Cor Sec 3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Mark A. Smith VAN BUREN CO REGISTERED SURVEYOR 7-00
Libert 5 Page 93 Register of Deeds Stamp & File Number

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked in cell I-2.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 GLO Set post at intersection Elm 20" S63°W 30 Links Elm 18" S01°E 93 Links 41.02 = 1/2 mile to South
I-1 Recorded Survey L.4, P.1 8-23-73 Set 5/8" iron from computes of work done by Don Ratekin. No witnesses show NE Cor. 518.49' East of iron on baseline and in centerline of 3850th Avenue.
I-1 Survey By Don R. Gilchrist & Associates 9-5-90. Shows same relationship to iron 518.49' Westerly of I-1. No witnesses.
I-1 LCRC L2, P.187 12-5-73 Part A found and uses as found by Don Ratekin. Part B set by computes from A survey by Don Ratekin, set on baseline Part C: 5/8" iron on only high ground in Area. Iron is N45E 100.27 from NE corner
I-1 Survey 10-22-90 By Don R. Gilchrist & Associates Shows same relationship to iron 518.49' Westerly of I-1. No witnesses
I-1 Recorded Survey L.9, P.373 10-7-1992 Shows same relationship to iron 518.49 Westerly of I-1. No witnesses.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor Date D. R. G. 12/26/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" diameter iron in west side of 6" Ash. Iron is northeasterly 98.2 feet from a fence post. This might be a tie that LCRC L2, P.187 leaves unfinished (Iron is N45E 100.27 from NE corner). Iron is 0.42' south of town line as defined by a line between K-13 and H-13 of Cheshire Township(T1N R14W), Allegan County, MI. I-13 is in Eagle Lake.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 5/8" by 18" iron with 3" brass cap North 0.42 feet from 1/2" iron.
I-1 is 1233.13' Westerly of K-13 (SE Corner Section 35 T1N R14W). I-1 is on the town line as defined by a line between K-13 and H-13 of Cheshire Township(T1N R14W), Allegan County, MI.
Set PK nail and Van Buren County witness tag 0.7' above grade in E side 6" Maple N 10°W 3.41 ft
Set PK and Van Buren County witness tag 1.0' above grade in 6" Maple S 35°W 10.00 ft
Set PK nail and Van Buren County witness tag 1.3' above grade in SE side 6" Maple S 52°W 21.49ft
Set PK nail and Van Buren County witness tag 1.2' above grade in S side 4" Maple S 75°W 12.87ft

Signed by Robert E. Lemke

Date 12/3/97

FOR SDI CONSULTANTS, LTD.

Surveyor's Michigan License No. 40160