

SURVEY & REMONUMENTATION

JAN 14 1998

VAN BUREN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

FILED

Dec 26 10 56 AM '97

For corners in SECTION

Van Buren (County) Located In: Bloomingdale Twp. Corner Code # K-1

1. Public Land Survey T 1 S R 14W NE Cor Sec 2
T R
T R
T R
2. Property Controlling S 2 T 1 S R 14W For K-1
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column K and row 1.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 GLO K-1 Recorded Survey L.4, P.104 K-1 Recorded Survey K-1 LCRC
Set post at intersection 6-25-72 NW Cor Fd pipe 12" down L.4,P.190 6-26-73 L.2,P.197 12-6-73
Beech 8" S38°E 16 Links 12" Walnut NE 27.3' to centerline Shows same witnesses as Part A: T.A. Smith
Lynn 6" S72°W 32 Links street sign post NE 18.20 to C.L. L.4,P.104 Found stone in 1928, pipe
Surveyor ? 2" pipe mailbox support Shows K-1 to 1/8th Cor East set over stone in 1958 by
Date ? NE 18.20 to centerline of K-1 distance of 1328.09 Smith & Smith
No tie to Allegan corner Shows K-1 to L-1 distance of 2656.18 Part B: Found pipe 12" down
Show K-1 to K-2 distance of 2912.01 set iron rod to surface
GLO distance-2895.42 (43.87 ch) Part C: Same witnesses as
Survey REC. L.4,P.104.

K-1 Survey 10-26-88 K-1 Survey 10-26-88 K-1 Survey 7-19-94
Alpha Engineering Wightman-Moored, Inc. Wightman-Moored, Inc.
Shows distance from L-13 (S1/4 post Shows K-1 to 1/8th Corner Uses K-1, no ties.
Sec. 36 T.1 N., R.14 W.) East of K-1 distance as 1328.09
to K-1 to be 1423.99'

Validated by Peer Group in accordance with P.A. 345 of 1991 Van Buren County Surveyor Date D.R.L. 12/26/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found iron rod 0.2' below surface of road. Also found pipe 1" diameter (o.d.) in monument box 26.10' westerly of iron rod. Did not find any witnesses from information listed in Part A. Removed iron rod and found 1"(o.d.) pipe 1' below surface of road as referenced in LCRC L.2,P.197. Current measure from L-13 to K-1 is 1424.00'. Also A.J. Pierce notes from Aug. 1871 show distance from K-1 to M-13 (SE Cor. Sec. 36 T.1 N., R.14 W.) to be 17.68 chains (1166.88'), current measure is 1167.06'. And is accepted as a careful and faithful reestablishment of the position of the original closing corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-1 Slim line Harrison Marker in monument box.

Harrison Marker is 2.99 ft south of town line as defined by L-13 to M-13 on the south line of Cheshire Township (T 1 N, R 14 W), Allegan County, MI. K-1 to M-13 (SE Cor. Sec. 36 T.1 N., R.14 W.) measures easterly 1167.06 ft. Set PK nail and Van Buren County witness tag 3.0' above grade in S side 6" Poplar S 50°E 82.80 ft Set PK nail and Van Buren County witness tag 3.0' above grade in S side 6" Elm S 35°E 82.65 ft Set PK nail and Van Buren County witness tag in SE side in 8" Catalpa S 55°W 52.06 ft Fd 1"(od) iron pipe in monument box N85°W 26.03 ft Marker is 5.0' south of the centerline of Baseline Road and on the extension northerly of the west edge of bituminous of 36th Street.

Signed by Robert E Lemke Date 12/3/97

FOR SDI CONSULTANTS, LTD.

Surveyor's Michigan License No. 40160

FORM APPROVED BY MICHIGAN STATE BOARD OF