

SURVEY & REMONUMENTATION

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

Dec 26 10 58 AM '97

For corners in **SECTION**

Van Buren (County) Located in: Bloomingdale Twp. Corner Code # L-1

1. Public Land Survey T 1 S R 14W N. 1/4 Cor. Sec. 1 **(L-1)**
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Mark A. Smith
 VAN BUREN CO.
 REGISTERED SURVEYOR

Liber 5 Page 91
 Register of Deeds Stamp & File Number

7-00
0101 10 SURVEY
7665 12/26

I, Robert E. Lemke, in a field survey on August 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1 GLO not set	L-1 Recorded Survey L.4.P.104 6-25-72 K-1 to L-1 Dist. = 2656.18' No wit's to N.1/4 post	L-1 Recorded Survey L.4.P.190 6-26-73 found large stone, set iron Face RR tie fence post south is 35.0' South. Corner is 2' ± N. centerline of travel	L-1 LCRC L.2.P.199 12-6-73 iron rod Face RR tie fence post south is 35.0' South. Corner is 2'±N. centerline of travel Centerline of 18" Poplar - SE 53'.	L-1 Recorded Survey L.765,P.139 5-15-84 shows K-1 to the 1/8 post west of L-1 to measure 1328.09'
--------------------	---	--	---	---

Ratified by Peer Group in
 accordance with P.A. 345 of 1990
 Van Buren County Surveyor
 Date D. R. G. 12/26/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 5/8" iron with damaged yellow cap. Iron fits tie to railroad tie fence post and is 2' ± north of travel.
 This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-1 Slim line Harrison Marker in monument box.
 Harrison Marker is 2.95 ft south of town line as defined by L-13 of Cheshire Township (T 1 N, R 14 W), Allegan County, MI. to M-1 of Bloomingdale Township, Van Buren County. Marker is 1489.22 easterly of M-13.
 Set 1/2" iron rod with cap #40160 at north edge of pavement N 30° E 12.98 ft
 Set 1/2" iron rod with cap #40160 at north edge of pavement N 35° W 13.34 ft
 Set PK nail and Van Buren County witness tag 3.0' above grade in NE side of 4" Poplar S 60° E 85.49 ft
 Set PK nail and Van Buren County witness tag 4.3' above grade in W side of 6" Maple S 05° W 88.92 ft
 Marker is in centerline of Baseline Road

Signed by Robert E. Lemke Date 12/3/97
 FOR SDI CONSULTANTS, LTD.

Surveyor's Michigan License No. 40160