

JAN 14 1998

SECTION

VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 16 12 00 PM '97

Mark A. Smith
VAN BUREN COUNTY
RECORDATION DEPARTMENT

For corners in VAN BUREN COUNTY Located in: COLUMBIA TWP. Corner ID # NW COR. SEC 7 T1S,R15W SW COR. SEC 16 T1S,R15W

- 1. Public Land Survey T 1S R 15W A-3
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. Recorded Plat
- 5. Private Claims

Liber 5 PAGE 51
Register of Deeds Stamp & File Number

I, Alan Bartlett in a field survey on December 8 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(PLEASE SEE BACK PAGE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" IRON BAR DUG DOWN 2.0' AND FOUND PIECES OF CERAMIC JUG IN MONUMENT BOX 5' WEST OF CENTER LINE OF COUNTY ROAD 681 AS CALLED FOR IN PREVIOUS NOTES DATED 1901 AND 4/15/1952. VERIFIED CORNER USING EXISTING WITNESSES. THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS ON NOVEMBER 19 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 1/2" HARRISON MONUMENT IN MONUMENT BOX 5' WEST OF CENTER LINE OF COUNTY ROAD 681.

- | WITNESSES | |
|--------------|--|
| N48°E 34.36' | SET NAIL AND FLASHER IN WOOD POST AT RISER |
| N63°E 6.70' | 1 1/2" IRON IN MONUMENT BOX |
| N67°E 51.48' | FOUND NAIL IN POWER POLE |
| S44°E 50.60' | TOP CENTER LINE OF TELEPHONE RISER BOX |
| S57°E 50.49' | TOP CENTER LINE OF STEEL FENCE POST |
| S68°W 39.16' | NORTH EDGE OF STOP SIGN POST |

THIS CORNER IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Ratified by Peer Group in accordance with P.A. 345 of 1998
Van Buren County Surveyor

Date D. R. G., 12/16/97



Signed by Alan K. Bartlett
Surveyor's Michigan License No. 35988

Date 12/15/97

2/18/1830 GLO
WEST BETWEEN SECTION 6 AND 7 A DISTANCE OF 75.57 CHAINS (4987.62') INTERSECTED WEST BOUNDARY 15 LINKS (9.90')
NORTH OF POST. SET POST AT INTERSECTION CORNER TO SECTION 6 AND 7.

WITNESSES

HEMLOCK 11" EAST 18 LINKS
MAPLE 16" S10°E 27 LINKS

10/1/1901 W.H. GOSS BOOK 1 PAGE 88
(SHOWS 39.99½ CHAINS SOUTH 2639.67') FOUND PINE STAKE AND GALLON JUG WHITE COLOR(NO WITNESSES)

10/15/1901 NOTES PAGE 7 (JUG) WITNESSES TELEPHONE POLE SE 0.48 (31.66')

4/15/1952 W.Q. SMITH
FOUND GENEVA CORNER IRON SET R.R. SPIKE IN BLACKTOP PER JOG.

4/15/1952 FIELD NOTES
FOUND OLD BOTTLE UPSIDE DOWN, DROVE PIPE THRU IT AND SET R.R. SPIKE IN BLACKTOP 9.9' (15 LINKS) NORTH OLD
WITNESSES TO SPIKE O.K.

6/22/1972 G.MITCHELL LCRC LIBER1 PAGE 458
FOUND 1 1/4" IRON BAR

WITNESSES

STOP SIGN S20°E 34.60'
POWER POLE N5°E 19.10'
TEL. CABLE BOX S45°E 47.20'

NO DATE SOUTHWEST SURVEYS
FOUND R.R. SPIKE

WITNESSES

CENTER CABLE BOX S45°E 41.6'
CENTER CABLE BOX N45°E 35'
W.END 12" CMP S70°W 26.6'

12/8/1997 LANDMARK TECH ALAN BARTLETT RLS #35988
FOUND 1 1/4" IRON IN MONUMENT BOX

WITNESSES

N63°E 6.70' 1½" IRON IN MONUMENT BOX
N67°E 51.48' FOUND NAIL IN POWER POLE
S44°E 50.60' TOP CL OF RISER
S57°E 50.49' TOP CL OF RISER