

SURVEY & REMONUMENTATION

FILED

JAN 14 1998

**VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Dec 16 12 00 PM '97

SECTION

For corners in VAN BUREN COUNTY Located in: COLUMBIA TWP. Corner ID # SW COR. SEC 7 T1S,R15W

Mark A. Bartlett
VAN BUREN COUNTY
LICENSED LAND SURVEYOR

- 1. Public Land Survey T 1S R 15W A-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Liber 5 PAGE 55
Register of Deeds Stamp & File Number

I, Alan Bartlett in a field survey on December 8 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D. R. G. 12/16/97

A. Description of original monument and accessories and/or subsequent restoration:

- 2/6/1830 GLO INTERSECTED WEST BOUNDARY 37 LINKS SOUTH OF POST SET POST AT INTERSECTION CORNER TO SECTION 7 AND 18
- 10/15/1901 W.H. GOSS FOUND GREY STONE
- 4/15/1952 ROSALLA NOTES FOUND GREY STONE SET PIPE ON SOUTH SIDE IN CENTER LINE OF ROAD NORTH, SOUTH, AND EAST WITNESSES 8" ELM S15°E 81.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

USED GLO DISTANCE OF 37 LINKS (24.42') SOUTH OF M-5, GENEVA TOWNSHIP (NE CORNER OF SECTION 13) TO SET CORNER ON TOWNSHIP LINE BETWEEN M-5 AND M-6. THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTAION PEER GROUP OF SURVEYORS ON NOVEMBER 19 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 2 1/2" HARRISON MONUMENT AND MONUMENT BOX 8.25' EAST OF CENTER LINE OF COUNTY ROAD 681 WITNESSES N40°E 33.37' END OF CORRUGATED METAL PIPE NORTH 24.42' SE CORNER SECTION 12 / NE CORNER OF SECTION 13 S70°E 76.25' SET NAIL AND FLASHER IN 16" OAK N80°W 47.64' SET NAIL AND FLASHER IN POWER POLE

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by A. K. Bartlett Date 12/15/97
Surveyor's Michigan License No. 35988

