

NOV 15 1994

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 18 12 03 PM '94

COMMISSION
LIBER 4 PAGE 169

For corners in Columbia Township
Van Buren County (County)

Located In: Corner Code #

Mark A. Smith
VAN BUREN CO
REGISTER OF DEEDS

7.00

- 1. Public Land Survey T 1 S R 15 W C-7
COR
SE 1/4 Sec 18
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

10/18 0101 10 SURVEY

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald R. Gilchrist, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set stake: 28" hemlock N 24° W, 13 links; and 15" hemlock S 73° E 26 links.
On June 24, 1904, W. Goss showed distance to N of 19.90 3/4 ch. doubled.
He showed distance to E of 39.83 ch.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 5/14/92 found 1/2" iron rod over stone.
2.5' N C/L road E & W; 0.5' W C/L road to S; 8' E C/L road to North

Corner was field checked on 9/26/94 by D.R. Gilchrist, Co. Surveyor.
Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date D.R.G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On June 30, 1992, the Van Buren County Remonumentation Peer Group approved the permanent remonumentation of this corner. On July 2, 1992, 1/2" I.R. & stone were removed. The stone was replaced and a Harrison Marker stamped "County Surveyor" was set over the stone & 2" below existing grade.
T pole - S 60° E 49.20' PK nail in SW face
16" dia maple tree - N 25° E 85.50' PK nail in W face
18" dia maple tree - N 20° W 87.94' PK nail in E face
NE Cor Ho - S 45° W 66.18'
1' N of CL E & W Rd
On CL Rd S & 7' E CL Rd N

Signed by Donald R. Gilchrist Date 10/3/94
Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

