

SURVEY & RE-MONUMENTATION

FILED

NOV 15 1994

Oct 18 12 03 PM '94

LIBER 4 PAGE 77 COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Columbia Township

Van Buren County (County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S 15 W E-8
W 1/4 Post Sec 21
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Mark A. Smith VAN BUREN CO REGISTER OF DEEDS

7-00

Register of Deeds Stamp & File Number

10/18 0101 10SURVEY

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (1, K) contains 7361.

I, Donald R. Gilchrist, in a field survey on 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Witnesses: Pine, 36", N 66° W, 6 lks Beech, S 27 1/2° E 12 lks.

Filed 4/18/72 by D.A. Ratekin in Liber 1 Pg. 282. On 5/27/92 fd. RR spike as noted by Ratekin.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D.R.G. 10/18/94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner witnessed prior to road construction. On 7/27/92 after road construction, set cap in asphalt over RR spike 2" below surface. RR spike w/cap over, 3.5' E C/L CR 215 & 2' S C/L 14th Ave. W. & 6' S 14th Ave. E.

Corner approved by County Peer Group and marker set in 1992. Field checked on 9/26/94 by D.R. Gilchrist, Co.Surveyor. Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

W 1/4 Post - Removed RR spike. Found 1 I.P. w/ small stones around, under. Drove pipe down. Set Harrison Marker over. New pole - S 40° W 78.60' PK nail SE face New pole - N 25° W 101.27' PK nail E face Clump of 15-24" dia. maples - N 10° E 102.53' PK nail W face Steel post for Dead End sign S 87° E 68.35' NW cor. 3.7' E of CL of N&S Rd.

Signed by Donald R. Gilchrist Date 10/13/94 Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

