

NOV 15 1994

FILED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE OCT 18 12 03 PM '94
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 17D

For corners in Columbia Township
Van Buren County (County) Located In: Corner Code =#

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

- 1. Public Land Survey T 1 S R15 W E-9
SW Cor Sec 21 T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

7.00
10/18 0101 10SURVEY

I, Donald R. Gilchrist, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Witnesses: Beech, 5", N 23° W, 9 lks
Beech, 14" S 70° E, 30 lks

Filed in Liber 1 on page 282 by D.A. Ratekin 4/18/72. On 5/27/92 fd. 1/2" I.P. as noted by Ratekin.

Ratified by Peer Group in accordance with P.A. 345 of 1998
Van Buren County Surveyor

Date D. R. G. 10/18/94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner witnessed prior to road construction. On 7/27/92 after road construction, set 1/2" I.R. w/cap over. 1/2" I.R. 4.5' W of C/L CR 215 & 5' N of C/L 16th Ave.

Corner approved by County Peer Group and marker set in 1992. Field checked on 9/26/94 by D.R. Gilchrist, Co. Surveyor. Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SW Corner - removed existing irons and replaced with Harrison Marker.
Face pole - S 86° E 38.99' PK nail N
Face pole - N 46° E 45.24' PK nail N
28" dia. oak - S 50° W 91.71' PK SE face
Steel post at Sw cor. C.P. Substation - E 63.30', W face
Steel post at NW cor. C.P. Substation - N 45° E 74.70' W face
CL Rd is 4.3' E

Signed by Donald R. Gilchrist Date 10/3/94
Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

