

1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 15 2 52 PM '93

For corners in COMMISSION  
VAN BUREN

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS

9.00

5125 11/15 0101 10SURVEY

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

(County) \_\_\_\_\_

N 1/4 CORNER, SEC. 23, COLUMBIA TOWNSHIP

1. Public Land Survey T 1S R 15W J-7

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, G. J. MITCHELL, in a field survey on NOVEMBER 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**\*SEE BACK OF SHEET\***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG HOLE AT "T" FENCE POST LOCATION AND FOUND LARGE STONE APPROXIMATELY 2.5' DEEP. STONE WAS OVAL SHAPED (APPROX. 12" W x 24" L) WITH NO VISIBLE MARKINGS. "T" FENCE POST WAS SLANTED OVER CENTER OF STONE. SET STANDARD MONUMENT OVER FENCE POST AFTER ROAD CONSTRUCTION BY V.B.C.R.C.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD MONUMENT

- 60d NAIL IN S. SIDE P. POLE N 60° W 161.91'
- 60d NAIL IN N. SIDE 10" PINE S 55° W 97.36'
- 60d NAIL IN S. SIDE P. POLE N 70° E 160.78'
- 60d NAIL IN N. SIDE P. POLE S 65° E 164.82'



Signed by *George J. Mitchell*  
 Surveyor's Michigan License No. 19618

Date November 11, 1993

NORTH QUARTER CORNER OF SECTION 23,  
TOWN 1 SOUTH, RANGE 15 WEST, COLUMBIA TOWNSHIP

GOVERNMENT - (1830)

SET 1/4 POST AT 40.50 CH = 2673.0'  
6" BEECH - S 18 DEG W - 7 LKS.  
14" BIRCH - N 83 DEG W - 13 LKS.

A. J. PIERCE, CO SURVEYOR - (3/11/70)

WIT & STAKE GONE.

S a TAMIRACK STAKE ON THE BI SECTION AT 40.225 CH = 2654.85'  
8" ELM - N 73 DEG 30' E - 70 LKS.

T.A. SMITH, CO SURVEYOR - (1946)

FD LARGE STONE - DROVE PIPE E SIDE OF STONE.  
DOUBLE 5" WAL - N 5.9' TO CEN LINE  
15" MAPLE - S 72 DEG W - 80.0' TO CEN LINE.  
PIPE 6' N OF CEN LINE RD. & 6' E OF CEN LINE RD S.  
DIST TO NE CORNER = 2658.2'.

W.Q. SMITH - (8/29/73)

FD "T" FENCE POST - FROM OLD WIT & DIST TO NE CORNER = 2658.03'.  
WIT AS REC - L2-P201.

GOVE ASSOC - (1990)

FD CORNER FROM REC WIT.  
36" BASSWOOD N 30 DEG E - 27.50' N & C.  
TRIPLE 18" BASSWOOD - N 50 DEG W - 72.80'.  
6" ELM - N 10 DEG W - 32.48'.

*LIBER 4 PAGE 74*