

JAN 14 1998

FILED

SECTION

VAN BUREN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 16 12 00 PM '97

For corners in VAN BUREN COUNTY Located in: GENEVA TWP. Corner ID # SE COR. SEC 1 T1S,R16W

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

- 1. Public Land Survey T 1S R 16W M-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____

Liber 5 Page 54

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

7478 12/16 0101 10SURVEY 7-00

I, Alan Bartlett in a field survey on December 8 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date D. R. G. 12/16/97

A. Description of original monument and accessories and/or subsequent restoration:

- 5/15/1827 WM. BROOKFIELD
NORTH ON EAST BOUNDARY OF SECTION 12, 80.00 SET POST CORNER TO SECTION 1 AND 12
WITNESSES
MAPLE 8" S7½°W 11 LINKS
PINE 15" N30°W 28 LINKS
- 4/15/1952 SHOWS 2584.45' TO NORTH ¼ POST AND 2606.02' TO EAST ¼ POST, SHOWS ANGLE 90° 10' FROM EAST ¼ TO NORTH ¼ CORNER. NOTES: FOUND OLD BOTTLE UPSIDE DOWN, DROVE PIPE THRU IT AND SET R.R. SPIKE IN BLACKTOP 9.9' (15 LINKS) NORTH
- BOOK 54 SOUTHWEST SURVEYS
NORTHEAST CORNER SECTION 12-1-16 IS 3.0' NORTH OF LINE BETWEEN NORTHWEST AND NORTH ¼ POST. IRON ROD FOUND. ANGLE 89°55'35" FROM EAST ¼ TO NORTH ¼ CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MEASURED 9.90' SOUTH OF A-3 ON TOWNSHIP LINE AS DETERMINED BY A-3 TO M-5 (ONLY EXISTING CORNERS), AT DEPTH OF 2' FOUND PIECES OF OLD BOTTLE AS CALLED FOR IN NOTES OF 4/15/1952. THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS ON NOVEMBER 19 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 2½" HARRISON MONUMENT AND MONUMENT BOX 5' WEST OF CENTER LINE OF COUNTY ROAD 681.
WITNESSES
- N38°E 41.64' SET NAIL AND FLASHER IN WOOD POST AT TELEPHONE RISER
- N58°E 56.08' FOUND NAIL IN POWER POLE
- S54°E 44.10' TOP OF TELEPHONE RISER @ CENTER LINE
- S77°E 45.86' TOP CENTER LINE OF FENCE POST
- S83°W 36.56' NORTH EDGE OF STOP SIGN POST
- NORTH 9.90' NW CORNER OF SECTION 7
- N25°E 14.23' 1½" IRON IN MONUMENT BOX

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Alan H. Bartlett
Surveyors Michigan License No. 35988

Date 12/15/97

