

JAN 14 1998

FILED

SECTION

VAN BUREN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 16 12 00 PM '97

For corners in VAN BUREN COUNTY Located in: GENEVA TWP. Corner ID # E 1/4 COR. SEC 12 T1S,R16W

Mark A. Smith VAN BUREN CO. SURVEYOR

- 1. Public Land Survey T 1S R 15W M-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Liber 5 Page 59 Register of Deeds Stamp & File Number

I, Alan Bartlett in a field survey on December 8 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (4,12) contains a dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 5/15/1827 GLO WM. BROOKFIELD 40.00 SET Q. SEC. POST WITNESSES MAPLE 16" S28 1/2 W 14 LINKS W. ASH 11" N64 1/2 W 16 LINKS
4/15/1952 ROSALLA NOTES 1/2 MILE NORTH 2606.02' 1/2 MILE SOUTH 2638.34'

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D. R. G. 12/16/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ESTABLISHED CORNER BY PRORATING DISTANCE BETWEEN M-3 AND M-5 AGAINST 1952 SURVEY 1/2 MILE DISTANCE AND SET ON LINE BETWEEN M3 AND M5. THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS ON NOVEMBER 19 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 1/2" HARRISON MONUMENT AND MONUMENT BOX 2.5' EAST OF CENTER LINE OF COUNTY ROAD 681

WITNESSES

- N64e 80.35 SET NAIL AND FLASHER IN NORTH SIDE OF 8" LOCUST
S59E 60.82 SET NAIL AND FLASHER IN POWER POLE
South 23.45 W 1/4 CORNER OF SECTION 7 T1S,R15W
N60W 65.03 TOP CENTER LINE OF STEEL FENCE POST

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by Alan K. Bartlett Date 12/15/97 Surveyor's Michigan License No. 35988

